

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: MORTON SW 1/4 SW 1/4 NE 1/4 23 T 33 S R 42 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM ELKHART ON HIGHWAY 27 - 12 NORTH, 2 1/2 EAST & 1/4 SOUT

2 WATER WELL OWNER: CIMARRON NATIONAL GRASSLAND  
 RR#, St. Address, Box #: PO BOX 300 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: ELKHART, KS 67950- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1 2 3 4 5 6 7 8 9 10	NW NE <b>X</b> SW SE	W E	
---	----------------------------------	--------	--

4 DEPTH OF COMPLETED WELL 355 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 104 ft. below land surface measured on no/day/yr 06/06/06  
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 9 in. to 355 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC  
 Blank casing diameter 5 in. to 355 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 17  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 290 ft. to 350 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 355 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: ABANDONED WELL  
 Direction from well? SOUTHWEST How many feet? 30

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	40	32 TAN CLAY			
40	60	32 TAN CLAY 26 RED CLAY			
60	80	32 TAN CLAY 02 FINE SAND			
80	100	02 FINE SAND 32 TAN CLAY 24 THINROCLAYER			
100	120	32 TAN CLAY 02 FINE SAND			
120	140	10 FINE-MEDSAND 05 CLAY			
140	160	32 TAN CLAY 02 FINE SAND			
160	190	10 FINE-MEDSAND			
190	200	05 CLAY 02 FINE SAND 19 LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 06/07/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 06/23/06 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Creek*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:      Fraction      Section Number      Township Number      Range Number  
COUNTY: MORTON      SW 1/4 SW 1/4 NE 1/4      23      T 33 S      R 42 W

2 WATER WELL OWNER:      CIMARRON NATIONAL GRASSLAND  
RR#, St. Address, Box #: PO BOX 300      Board of Agriculture, Division of Water Resources  
City, State, ZIP code : ELKHART, KS 67950-      Application Number:

FROM	TO	LITHOLOGIC LOG
200	220	02 FINE SAND 24 THINROCLAYER
220	240	29 SANDSTONE
240	260	29 SANDSTONE 20 RED SHALE
260	355	29 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/07/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179      This Water Well Record was completed on (mo/day/yr) 06/23/06 under the business name of JOB'S WELL SERVICE, INC.      by (signature) *Judith Creek*