

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

Adams #1

Invoice #


kismet SE

1 Location of well:	County Meade	Township name	Fraction B C NW SW	Section number 32	Town number 34S	Range number 29W
---------------------	------------------------	---------------	----------------------------------	-----------------------------	---------------------------	----------------------------

Distance and direction from nearest town or city: **6 Miles South of Meade St. Lake on Hwy 23**
Street address of well location if in city:

3 Owner of well: **Rine Drilling Co. Rig #8**
Suite 600
Address: **300 W. Douglas**
Wichita, Kansas 67202

Locate with "X" in section below:



Sketch map:
Meade Lake
6 mi S Hwy 23
Loc. X

4 Well depth: **380** ft. Date of completion **2/4/75**
Well diameter **9** in.

5 Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

6 Use: Domestic Public supply Industry
 Irrigation Air conditioning Commercial
 Test well Oil Well

7 Casing: Material **PVC** Height: above/below
Threaded Welded Surface **18** in.
Diam. **5 1/2** in. to **300** ft. depth Drive shoe? Yes No
5 1/2 in. to **380** ft. depth!

2	Type and color of material	From	To
	Surface	0	2
	Tan Clay	2	56
	Sand	56	60
	Fine Sand w/Clay Streaks	60	143
	Brown Clay w/Sand Streaks	143	160
	Brown Clay	160	200
	Brown Clay w/Sand Streaks	200	214
	Brown Clay	214	220
	Brown & Pink Clay w/Sand Streaks	220	240
	Pink Clay w/Sand Streaks	240	290
	White Clay w/Sand Streaks	290	300
	Fine to Medium Sand w/Clay Streaks	300	320
	Medium Sand	320	340
	Medium Sand w/Clay Streaks	340	363
	White Clay w/Sand Streaks <i>BR</i>	363	380

8 Screen:
Manufacturer **Wesco**
Type **PVC** Dia. **5 1/2"**
Slot/gauze **.030** Length **10'**
Set between **330** ft. and **340** ft.
Fittings:
Gravel pack Yes No Size range of material _____

9 Static water level:
200 ft. below land surface Date **2/4/75**

10 Pumping level below land surfaces:
_____ ft. after _____ hrs. pumping _____ g.p.m.
_____ ft. after _____ hrs. pumping _____ g.p.m.
Estimated maximum yield **50** g.p.m.

11 Water sample submitted:
 Yes No Date _____

12 Well head completion:
 Pitless adapter **18** inches above grade

13 Well grouted? Yes No
 Neat cement Bentonite _____
Depth: From **200** ft. to **380** ft.

14 Nearest source of possible contamination:
ft. **100** Direction **SW** Type **Oil Well**
Well disinfected upon completion? Yes No

15 Pump: Not installed
Manufacturer's name _____
Model number _____ HP _____ Volts _____
Length of drop pipe _____ ft. capacity _____ g.m.p.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

16 Remarks: elevation

Topography:
 Hill
 Slope
 Upland
 Valley

17 Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Carlile Water Well 118
Business name License No.
Address **Box 275, Liberal, Kansas**
Signed **Edward A. Means** Date _____
Authorized representative

34 29W 32 NW SW