

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE : Near Center SW 1/4 : 05 : T 34 S : R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 9 1/2 SOUTH AND 1/2 WEST OF PLAINS WELL LOCATION

2 WATER WELL OWNER: HARDEN, DEAN
 RR#, St. Address, Box #: ROUTE 1 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: PLAINS, KS 67869- Application Number: 42,008

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 578 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 213 ft. below land surface measured on mo/day/yr 05/02/96
 Pump test data: Well water was 255 ft. after 4 hours pumping 1300 gpm
 Estimated Yield 1300 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 578 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 578 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 295 ft. to 395 ft., From 0 ft. to 0 ft.
 From 395 ft. to 575 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 578 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	30	04 SANDY CLAY 31 CALICHE			
30	45	01 CLAY 31 CALICHE			
45	125	05 SAND 31 CALICHE 01 CLAY			
125	155	05 SAND 01 CLAY			
155	165	05 SAND 01 CLAY			
165	180	01 CLAY 05 SAND			
180	260	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
260	365	05 SAND 01 CLAY			
360	365	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/01/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/07/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	NE 1/4 NE 1/4 SW 1/4	05	T 34 S	R 30 W

2 WATER WELL OWNER:	HARDEN, DEAN	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	ROUTE 1	Application Number: 42,008
City, State, ZIP code :	PLAINS, KS 67869-	

FROM	TO	LITHOLOGIC LOG
365	370	01 CLAY
370	440	05 SAND 01 CLAY
440	450	06 VERY FN SAND 07 FINE SAND 08 MEDIUM SAND
450	460	05 SAND 01 CLAY
460	465	01 CLAY 05 SAND
465	485	05 SAND 01 CLAY
485	505	01 CLAY 07 FINE SAND
505	575	05 SAND 01 CLAY 31 CALICHE
575	585	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/01/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/07/96 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmuth*