

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE SW 1/4 SE 1/4 SW 1/4 8 T 34 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 11 SOUTH AND 1/2 WEST OF PLAINS

2 WATER WELL OWNER: DEKALB SWINE BREEDERS

RR#, St. Address, Box #: P.O. BOX 429

City, State, ZIP code: PLAINS, KS 67869-

Board of Agriculture, Division of Water Resources

Application Number: 40,738

*Battery of two
Identical wells*

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 472 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 195 ft. below land surface measured on mo/day/yr 04/30/93
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 75 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 17.5 in. to 472 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 12 OTHER - *stock watering*

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

X

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 8 in. to 472 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. .410

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 292 ft. to 332 ft., From 412 ft. to 432 ft.

From 352 ft. to 372 ft., From 452 ft. to 472 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 472 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT

Grout intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	03 SILTY CLAY			
2	10	04 SANDY CLAY			
10	25	07 FINE SAND 08 MEDIUM SAND			
25	32	01 CLAY 31 CALICHE 01 CLAY			
32	54	01 CLAY			
54	58	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
58	82	04 SANDY CLAY 07 FINE SAND 20 LIMESTONE			
82	86	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
86	108	01 CLAY			
108	136	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 060 MEADE : SW 1/4 SE 1/4 SW 1/4 : 8 : T 34 S : R 30 W

2 WATER WELL OWNER: DEKALB SWINE BREEDERS
RR#, St. Address, Box #: P.O. BOX 429 Board of Agriculture, Division of Water Resources
City, State, ZIP code : PLAINS, KS 67869- Application Number: 40,738

FROM	TO	LITHOLOGIC LOG
136	142	01 CLAY
142	168	07 FINE SAND 08 MEDIUM SAND 01 CLAY
168	186	07 FINE SAND 08 MEDIUM SAND
186	216	07 FINE SAND 08 MEDIUM SAND 01 CLAY
216	340	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
340	356	04 SANDY CLAY 01 CLAY 07 FINE SAND
356	372	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
372	378	04 SANDY CLAY 01 CLAY
378	423	07 FINE SAND 08 MEDIUM SAND 01 CLAY
423	472	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
472	494	01 CLAY 07 FINE SAND

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/93
under the business name of HENKLE DRILLING & SUPPLY by (signature) Bruce J. Reichmuth