

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 088 SEWARD SE 1/4 SE 1/4 NW 1/4 20 T 34 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM HAYNE; APPX 1 MILE SOUTH & 1 3/4 MILES WEST

2 WATER WELL OWNER: LARRY HITTLE Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: RT 2 BOX 294 Application Number: 45,737  
 City, State, ZIP code: LIBERAL, KS 67901-9139

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 375 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 206 ft. below land surface measured on mo/day/yr 09/14/04  
 Pump test data: Well water was 261 ft. after 4 hours pumping 1200 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 375 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

1	NW	NE
M i l e	X	E
	SW	SE

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 375 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 243 ft. to 283 ft., From 0 ft. to 0 ft.  
 From 283 ft. to 363 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 375 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	18	04 SANDY CLAY 31 CALICHE			
18	33	04 SANDY CLAY			
33	73	04 SANDY CLAY 05 SAND			
73	94	05 SAND 13 FINE GRAVEL 01 CLAY			
94	99	04 SANDY CLAY			
99	123	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
123	212	05 SAND 11 GRAVEL 01 CLAY			
212	233	04 SANDY CLAY 05 SAND			
233	266	05 SAND 13 FINE GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/10/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/05/04 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 088 SEWARD	Fraction SE 1/4 SE 1/4 NW 1/4	Section Number 20	Township Number T 34 S	Range Number R 32 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :	LARRY HITTLE RT 2 BOX 294 LIBERAL, KS 67901-9139	Board of Agriculture, Division of Water Resources Application Number: 45,737
---	--	---

FROM	TO	LITHOLOGIC LOG
266	290	05 SAND 13 FINE GRAVEL 01 CLAY
290	307	05 SAND 01 CLAY
307	363	05 SAND 01 CLAY
363	378	07 FINE SAND 08 MEDIUM SAND 01 CLAY
378	400	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/10/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/05/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bernie Reichert*