

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number  
 COUNTY: 088 SEWARD : SE 1/4 NE 1/4 SW 1/4 : 17 : T 34 S : R 32 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 5 MILES EAST AND 2 1/2 NORTH OF LIBERAL

2 WATER WELL OWNER: KANSAS DEPT. OF TRANSPORT.  
 RR#, St. Address, Box #: P. O. BOX 324 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : LIBERAL, KS 67901- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 400 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 227 ft. below land surface measured on mo/day/yr 01/08/93  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter in. to 0 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 6 in. to 400 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 260 ft. to 280 ft., From 360 ft. to 400 ft.  
 From 300 ft. to 320 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 400 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT  
 Grout intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	36	04 SANDY CLAY 07 FINE SAND			
36	78	01 CLAY 20 LIMESTONE			
78	86	07 FINE SAND 08 MEDIUM SAND			
86	90	04 SANDY CLAY 20 LIMESTONE			
90	143	01 CLAY 20 LIMESTONE			
143	165	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
165	173	01 CLAY 20 LIMESTONE			
173	210	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
210	214	01 CLAY 07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/15/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:     : Fraction                             : Section Number     : Township Number     : Range Number  
COUNTY: 088 SEWARD           : SE    1/4 NE    1/4 SW    1/4     : 17                   : T 34                S             : R 32    W

2 WATER WELL OWNER:            KANSAS DEPT. OF TRANSPORT.

RR#, St. Address, Box # : P. O. BOX 324

City, State, ZIP code : LIBERAL, KS    67901-

Board of Agriculture, Division of Water Resources  
Application Number:

FROM	TO	LITHOLOGIC LOG
214	245	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
245	251	04 SANDY CLAY 20 LIMESTONE
251	283	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
283	293	04 SANDY CLAY
293	300	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
300	310	04 SANDY CLAY 05 SAND
310	315	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
315	320	04 SANDY CLAY
320	345	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
345	394	04 SANDY CLAY 07 FINE SAND
394	400	04 SANDY CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year)            and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145            This Water Well Record was completed on (mo/day/yr) 01/15/93 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bruce Reichmuth*