

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 088 SEWARD | NW 1/4 SW 1/4 NW 1/4 | 24 | T 34 S | R 33 W

Distance and direction from nearest town or city street address of well if located within city?
FROM LIBERAL, APPX 2 MILES NORTH & 2 MILES EAST

2 WATER WELL OWNER: NATIONAL BEEF PACKING CO
 RR#, St. Address, Box #: PO BOX 978 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LIBERAL, KS 67901-0978 Application Number:

3 LOCATE WELL'S LOCATION WITH | 4 DEPTH OF COMPLETED WELL 640 ELEVATION: 0
 AN "X" IN SECTION BOX: | Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 206 ft. below land surface measured on mo/day/yr 8/23/06
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 12.25 in. to 640 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 10 MONITORING
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTHER - CERTI LOK
 Blank casing diameter 5 in. to 640 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .327
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 300 ft. to 320 ft., From 420 ft. to 440 ft.
 From 380 ft. to 400 ft., From 460 ft. to 480 ft.
 GRAVEL PACK INTERVALS: From 208 ft. to 640 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 208 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	5	01 CLAY			
5	57	07 FINE SAND 01 CLAY			
57	70	01 CLAY 20 LIMESTONE			
70	80	01 CLAY			
80	85	07 FINE SAND			
85	101	04 SANDY CLAY 05 SAND			
101	165	01 CLAY 05 SAND 20 LIMESTONE			
163	474	05 SAND 01 CLAY			
190	208	01 CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/25/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/20/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 088 SEWARD	NW 1/4 SW 1/4 NW 1/4	24	T 34 S	R 33 W

2 WATER WELL OWNER: NATIONAL BEEF PACKING CO
 RR#, St. Address, Box # : PO BOX 978 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : LIBERAL, KS 67901-0978 Application Number: |

SCREEN PERFORATED INTERVALS: From 500 ft. to 520 ft., From 580 ft. to 600 ft.
 From 540 ft. to 560 ft., From 620 ft. to 640 ft.

FROM	TO	LITHOLOGIC LOG
208	217	07 FINE SAND 01 CLAY
217	243	05 SAND 13 FINE GRAVEL 01 CLAY
243	260	01 CLAY 07 FINE SAND
260	268	07 FINE SAND 01 CLAY
268	274	07 FINE SAND 08 MEDIUM SAND 01 CLAY
274	290	01 CLAY
290	301	01 CLAY 20 LIMESTONE
301	312	07 FINE SAND 01 CLAY
312	356	01 CLAY
356	362	20 LIMESTONE
362	382	01 CLAY
382	397	01 CLAY
397	412	01 CLAY
412	428	01 CLAY
428	454	01 CLAY 05 SAND
454	463	20 LIMESTONE 01 CLAY
474	483	01 CLAY 05 SAND
483	525	05 SAND 01 CLAY
525	543	01 CLAY 05 SAND
543	554	07 FINE SAND 01 CLAY
554	563	01 CLAY
563	578	07 FINE SAND 01 CLAY
578	588	07 FINE SAND 01 CLAY
588	637	06 VERY FN SAND 07 FINE SAND 01 CLAY
637	650	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/25/06 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/20/06
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Brian J. Henkle