

DRILLERS TEST LOG

CUSTOMERS NAME National Beef Packing Co. DATE 4-1-87
 STREET ADDRESS 1501 E. 8th TEST # 1 E. LOG Yes - 100'
 CITY & STATE Liberal, KS 67901 DRILLER Livingston
 COUNTY Seward QUARTER NE SECTION 27 TOWNSHIP 34 RANGE 33
 LOCATION 1975 ft. south and 680 ft. west of Northeast Section 27 corner.
NW $\frac{1}{2}$. SE $\frac{1}{2}$ NE $\frac{1}{2}$. Sec. 27. T. 34. R. 33 W

%	FOOTAGE		DESCRIPTION OF STRATA	Static Water Level
	From	Pay To		Proposed Well Depth
	0	4	Sand	
	4	16	Sand, fine and sandy clay	
	16	27	Brown sandy clay	
	27	41	Brown clay	
	41	48	Sandy clay, caliche	
	48	55	Sand, fine and sandy clay	
	55	58	Sandy clay	
	58	69	Brown sandy clay, caliche	
	69	74	White sandy clay and caliche	
	74	79	Sand, fine	
	79	83	White clay	
	83	92	Sand, fine to medium, coarse, few small gravel	
	92	171	Brown clay and limerock ledges	
	171	10 180	Sand, fine to medium, coarse	
	180	190	Sandy clay and few sand stks.	
	190	14 204	Sandy clay and sand, fine to medium, stks.	
	204	207	Brown sandy clay	
	207	29 236	Sand, fine to medium, coarse, and few small gravel and clay stks.	
	236	240	Brown sandy clay	
	240	07 247	Sand, fine to medum	
	247	251	Blue clay	
			TOTAL DEPTH: 250'	
			5" PVC	
			PERF	PLAIN
			250-130'	120'
			130-0'	130'
			TOTAL	120'
				130'
			250'	
			Pellets at 118'	13 Bags of Cement at 40'
			4 - Bags Jel	2 Bags of Quickette Cement
			100# Celca	
			Elev. Land Surface	2,821
			Airlift - 2 hrs. (4-2-87)	
			Airlift - 2 hrs. (4-3-87)	

GARDEN CITY, KS HENKLE DRILLING & SUPPLY CO., INC. SUBLETTE, KS
 Phone 276-3278 IRRIGATION HEADQUARTERS Phone 675-4311
 TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS