

1 LOCATION OF WATER WELL: County: <u>Seward</u>	Fraction <u>NE 1/4 NW 1/4 NE 1/4</u>	Section Number <u>29</u>	Township Number <u>T 34 S</u>	Range Number <u>R 33</u> EW
--	---	-----------------------------	----------------------------------	--

Distance and direction from nearest town or city street address of well if located within city?
From Tucker Road and Hwy 83 north part of Liberal, 3/8 west on south side

2 WATER WELL OWNER: <u>Owsley Enterprises</u> RR#, St. Address, Box # : <u>13 Plaza Drive</u> City, State, ZIP Code : <u>Liberal, KS 67901</u>	Board of Agriculture, Division of Water Resources Application Number: <u>36,951</u>
--	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL <u>245</u> ft. ELEVATION: _____
--	---

Depth(s) Groundwater Encountered 1. 122 ft. 2. _____ ft. 3. _____ ft.

WELL'S STATIC WATER LEVEL 122 ft. below land surface measured on 9-24-84 mo/day/yr

Pump test data: Well water was 170 ft. after 1 hours pumping 346 gpm

Est. Yield 600 gpm: Well water was 216 ft. after 3 hours pumping 570 gpm

Bore Hole Diameter 18 in. to 245 ft., and _____ in. to _____ ft.

WELL WATER TO BE USED AS:

5 Public water supply	8 Air conditioning	11 Injection well
1 Domestic	3 Feedlot	6 Oil field water supply
2 Irrigation	4 Industrial	7 Lawn and garden only
		10 Observation well

Was a chemical/bacteriological sample submitted to Department? Yes _____ No X; If yes, mo/day/yr sample was submitted _____

Water Well Disinfected? Yes X No _____

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued _____ Clamped _____
<u>1 Steel</u>	3 RMP (SR)	6 Asbestos-Cement	<u>Welded</u>
2 PVC	4 ABS	7 Fiberglass	Threaded _____

Blank casing diameter 10 3/4 in. to 245 ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.

Casing height above land surface 24 in., weight 31.20 lbs./ft. Wall thickness or gauge No. 279

TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC	10 Asbestos-cement
<u>1 Steel</u>	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
			11 Other (specify) _____
			12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot	<u>3 Mill slot</u>	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes	
		7 Torch cut	10 Other (specify) _____	

SCREEN-PERFORATED INTERVALS: From 180 ft. to 240 ft., From _____ ft. to _____ ft.

GRAVEL PACK INTERVALS: From 20 ft. to 245 ft., From _____ ft. to _____ ft.

6 GROUT MATERIAL:	1 Neat cement	<u>2 Cement grout</u>	3 Bentonite	4 Other _____
-------------------	---------------	-----------------------	-------------	---------------

Grout Intervals: From 0 ft. to 20 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.

What is the nearest source of possible contamination:

1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	<u>none observed</u>

Direction from well? _____ How many feet? _____

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
		See attached log			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>September 19, 1984</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>145</u> . This Water Well Record was completed on (mo/day/yr) <u>October 9, 1984</u> under the business name of <u>Henkle Drilling & Supply Co., Inc.</u> by (signature) <u>Bruce J. Reichmuth</u>	
---	--

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY
T
R
EW
SEC
1/4
1/4
1/4

DF

