

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Seward	Fraction SE 1/4 SE 1/4 NW 1/4	Section number 10	Township number T 34 S R 34 E/W	Range number 34
2. Distance and direction from nearest town or city: 4 miles N, 4 1/2 miles W & 1/2 S of Liberal, Kansas Street address of well location if in city:			3. Owner of well: Wayne Wettstein R.R. or street: R.R. City, state, zip code: Liberal, Kansas		
4. Locate with "X" in section below:		Sketch map: SE corner of the NW 1/4, Sec. 10, T34S, R34W, Seward Co., Kansas			
5. Type and color of material		From	To	6. Bore hole dia. 28 in. Completion date 3-16-76 Well depth 600 ft.	
Top soil		0	3	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Fine sand		3	22	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Brown Clay		22	35	9. Casing: Material STL Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft. Dia. 16 in. to 198 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. .219	
Fine sand		35	46	10. Screen: Manufacturer's name Cook and Foster wire wrap Type Millislot Dia. 16" Slot/gauze 1/8" Length 402' Set between 198 ft. and 600 ft. ft. and <input type="checkbox"/> ft. Gravel pack? Yes Size range of material 3mm	
Brown clay		46	54	11. Static water level: <input type="checkbox"/> mo./day/yr. 180 ft. below land surface Date 10-9-75	
Fine to coarse sand		54	66	12. Pumping level below land surfaces: 325 ft. after 1 hrs. pumping 1336 g.p.m. 334 ft. after 1 hrs. pumping 1266 g.p.m. Estimated maximum yield 1200 g.p.m.	
Tan clay		66	80	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>	
Fine to coarse sand		80	114	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> <input type="checkbox"/> Inches above grade	
Tan & white clay with caliche streaks		114	190	15. Well grouted? Yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.	
Fine to coarse sand		190	218	16. Nearest source of possible contamination: Unk ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Very fine to fine sand		218	224	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 12KEH HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe 400 ft. capacity 1800 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Fine to coarse sand some clay lenses		224	262		
Fine to medium sand lots of clay lenses		262	420		
Fine to medium sand some clay lenses		420	536		
Fine to medium sand some clay lenses		536	600		
(Use a second sheet if needed)					
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne - Western Co. 150 Business name License No. Address Garden City Signed R. Vincent Date 21 May 76 Authorized representative	
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

34
 T
 34
 R
 10
 Sec
 1/4
 1/4
 1/4
 S
 E
 S
 E
 W
 W

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5