

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Seward	Fraction SE 1/4 NW 1/4 NW 1/4	Section number 26	Township number T 34 S R 34 E/W	Range number
2. Distance and direction from nearest town or city: 4 Miles west of Liberal			3. Owner of well: Ken Powell R.R. or street: 1012 Harrison Circle City, state, zip code: Liberal, Kansas		
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: Center of the NW₄, Sec. 26, T34S, R34W, Seward County, Kansas.		
5. Type and color of material			From	To	6. Bore hole dia. 28 in. Completion date 8-28-76 Well depth 477 ft.
Fine sand			0	10	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Fine sand clay streaks			10	30	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Mixed colored clay			30	38	9. Casing: Material Stl Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft. Dia. 1 1/2 in. to 199 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219
Fine sand clay streaks			38	82	10. Screen: Manufacturer's name Doerr, Foster Type Louver, mildst 16" Slot/gauze 1/8" Length 278 Set between 199 ft. and 477 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 3 mm
Tan clay sand streaks			82	195	11. Static water level: <input type="checkbox"/> mo./day/yr. 132 ft. below land surface Date 7-6-76
Fine to coarse sand clay streaks			195	241	12. Pumping level below land surfaces: 240 ft. after 1/2 hrs. pumping 1040 g.p.m. 296 ft. after 1 hrs. pumping 1566 g.p.m. Estimated maximum yield 1400 g.p.m.
Fine sand clay streaks			241	600	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date
					14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
					15. Well grouted? Yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.
					16. Nearest source of possible contamination: unk ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
					17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 12KEH HP 200 Volts Length of drop pipe 360 ft. capacity 1200 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
					(Use a second sheet if needed)
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Company, Inc. Business name License No. Address Garden City, Kansas Signed <i>[Signature]</i> Date 8 Nov 76 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

T 34 S R 34 E/W
 Sec 26
 1/4 1/4
 SE 1/4 NW 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5