


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Seward	Fraction NW 1/4 NW 1/4 NW 1/4	Section number 30	Township number T 34 S R 34 E	Range number 34
2. Distance and direction from nearest town or city: 6 Miles W and 3 miles N of Liberal Street address of well location if in city:				3. Owner of well: Mueller Trust R.R. or street: % First National Bank City, state, zip code: Wichita, Kansas		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 28 in. Completion date 15 Apr 76 Well depth 518 ft.		
		600' S of the NW corner of the NW 1/4, Sec. 30, T34S, R34W, Seward County, Kansas		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material				From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Top soil				0	3	9. Casing: Material STL Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft.
Fine sand, clay streaks				3	80	Dia. 16 in. to 236 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219
Tan clay				80	160	10. Screen: Manufacturer's name Brown Type Louver Dia. 16 in. Slot/gauze 1/8 in. Length 282 ft. Set between 236 ft. and 518 ft. ft. and <input type="checkbox"/> ft.
Caliche				160	186	Gravel pack? Yes Size range of material 3.0mm
Fine to coarse sand, clay streaks				186	380	11. Static water level: <input type="checkbox"/> mo./day/yr. 116 ft. below land surface Date 12-29-75
Fine to med. sand, clay streaks				380	748	12. Pumping level below land surfaces: 142 ft. after 1 hrs. pumping 1040 g.p.m. 186 ft. after 1 hrs. pumping 2550 g.p.m. Estimated maximum yield 3000 g.p.m.
Red bed				748	760	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
						14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
						15. Well grouted? Yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: Unk ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
						17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 12KM HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe 220 ft. capacity 900 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. Inc. 150 Business name License No. Address Garden City, Kansas Signed [Signature] Date 10 May 76 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5