

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SE 1/4 SE 1/4 NW 1/4 20 T 34 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 APPX 2 MILES WEST, 7 SOUTH, 1/2 WEST & 6/10 NORTH OF WOODS

2 WATER WELL OWNER: SKINNER, GARY
 RR#, St. Address, Box #: 109 N MAIN Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 42,131

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 665 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 194 ft. below land surface measured on mo/day/yr 02/05/98
 Pump testdata: Well water was 243 ft. after 4 hours pumping 1640 gpm
 Estimated Yield 1640 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 665 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 665 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 296 ft. to 316 ft., From 353 ft. to 653 ft.
 From 329 ft. to 339 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 658 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	28	07 FINE SAND 01 CLAY			
28	64	01 CLAY			
64	68	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
68	87	04 SANDY CLAY 05 SAND			
87	100	05 SAND 01 CLAY			
100	200	01 CLAY 05 SAND 20 Limestone			
200	210	05 SAND 28 ROCK 20 Limestone			
210	221	05 SAND 20 Limestone 01 CLAY			
221	240	01 CLAY 20 Limestone 05 SAND			
240	254	07 FINE SAND 08 MEDIUM SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/04/98 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/16/98
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 095 STEVENS SE 1/4 SE 1/4 NW 1/4 20 T 34 S R 35 W

2 WATER WELL OWNER: SKINNER, GARY

RR#, St. Address, Box #: 109 N MAIN

Board of Agriculture, Division of Water Resources

City, State, ZIP code : HUGOTON, KS 67951-

Application Number: 42,131

FROM	TO	LITHOLOGIC LOG
254	273	01 CLAY 07 FINE SAND
273	296	07 FINE SAND 01 CLAY
296	299	01 CLAY
299	316	05 SAND 01 CLAY 20 LIMESTONE
316	327	01 CLAY 05 SAND 20 LIMESTONE
327	340	05 SAND 01 CLAY 20 LIMESTONE
340	345	01 CLAY 05 SAND
345	369	29 ROCK & SAND 01 CLAY 20 LIMESTONE
369	400	05 SAND 01 CLAY 20 LIMESTONE
400	480	05 SAND 20 LIMESTONE 01 CLAY
480	540	05 SAND 01 CLAY 20 LIMESTONE
540	650	05 SAND 01 CLAY
650	655	07 FINE SAND 01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) 02/04/98 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/16/98
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Richman*