


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>STERENS</u>	Fraction <u>SE 1/4 SW 1/4 NE 1/4</u>	Section number <u>6</u>	Township number <u>T 34</u>	Range number <u>S R 36 E</u>
2. Distance and direction from nearest town or city:		<u>3 East 3 1/2 S</u>		3. Owner of well: <u>Charles M. Rataleiss</u>		
Street address of well location if in city:		<u>of Hugoton, Kz</u>		R.R. or street: City, state, zip code:		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>10</u> in. Completion date <u>5-23-77</u> Well depth <u>200</u> ft.		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☒ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>blow sand</u>		<u>0</u>	<u>10</u>	9. Casing: Material <u>Plastic</u> Height: <u>Above</u> or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☒ Weight <u>12</u> lbs./ft. Dia. <u>5</u> in. to <u>200</u> ft. depth Wall Thickness: inches or Dia. <u>5</u> in. to <u>200</u> ft. depth gage No. <u>250</u>		
<u>dark Gumbo - blue Gray shaley</u>		<u>10</u>	<u>31</u>	10. Screen: Manufacturer's name <u>Slocum</u> Type <u>Saw cut</u> Dia. <u>5"</u> Slot/gauze <u>1/4</u> Length <u>40'</u> Set between <u>160</u> ft. and <u>200</u> ft. Gravel pack? ☒ Size range of material <u>1/4" to 1/2"</u>		
<u>Sandy w/ blue clay balls</u>		<u>31</u>	<u>40</u>	11. Static water level: <u>115</u> ft. below land surface Date <u>5-23-77</u> mo./day/yr.		
<u>Sand buff F</u>		<u>40</u>	<u>50</u>	12. Pumping level below land surfaces: <u>baling</u> <u>balin</u> after <u>20</u> hrs. pumping <u>20</u> g.p.m. <u>120</u> ft. after <u>20</u> hrs. pumping <u>20</u> g.p.m. Estimated maximum yield <u>100</u> g.p.m.		
<u>Clays Tan Gray rust + black + red</u>		<u>50</u>	<u>54</u>	13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>5-23-77</u> mo./day/yr.		
<u>Sand w/ scattered Pinches of clay redish</u>		<u>54</u>	<u>108</u>	14. Well head completion: ☐ Pitless adapter <u>12</u> Inches above grade		
<u>Clay - Cocoa Colored w/ sand</u>		<u>108</u>	<u>116</u>	15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
<u>Sand w/ some rocks</u>		<u>116</u>	<u>120</u>	16. Nearest source of possible contamination: <u>not known</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? ☒ Yes ☐ No		
<u>Gravel F. w/ redish clay</u>		<u>120</u>	<u>148</u>	17. Pump: <u>not installed</u> ☐ Not installed Manufacturer's name <u> </u> HP <u> </u> Volts <u> </u> Model number <u> </u> Length of drop pipe <u>140</u> ft. capacity <u>3</u> g.p.m. Type: <u>Windmill</u> ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
<u>Caliche hard + soft w/ some silt balls + Gravel</u>		<u>148</u>	<u>157</u>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Slocum well Drilling</u> <u>127</u> Business name License No. Address <u>Hugoton, Kansas 67951</u> Signed <u>Paul Slocum</u> Date <u>6-20-77</u> Authorized representative		
<u>brown silt balls</u>		<u>157</u>	<u>160</u>			
<u>Sand Cr brown</u>		<u>160</u>	<u>166</u>			
<u>silt balls brown + clay shell</u>		<u>166</u>	<u>180</u>			
<u>Clay balls "</u>		<u>180</u>	<u>190</u>			
<u>Clay balls " white w/ sand F. to C.</u>		<u>190</u>	<u>200</u>			
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley						