

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
 COUNTY: 095 STEVENS : NE 1/4 NE 1/4 NW 1/4 : 04 : T 34 S : R 38 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 1 3/4 MILES SOUTH & 1 1/2 MILES EAST OF FETERITA

2 WATER WELL OWNER: GREWELL, PAUL
 RR#, St. Address, Box #: ROUTE 1, BOX 107E Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 42,338

3 LOCATE WELL'S LOCATION WITH : 4 DEPTH OF COMPLETED WELL 519 ELEVATION: 0
 AN "X" IN SECTION BOX: : Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 / \ X : WELL'S STATIC WATER LEVEL 356 ft. below land surface measured on mo/day/yr 01/25/97 :
 : Pump test data: Well water was 255 ft. after 4 hours pumping 1565 gpm :
 1 NW NE : Estimated Yield 1565 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm :
 W : Bare Hole Diameter 24 in. to 519 ft., and in. to 0 ft. :
 E : WELL WATER TO BE USED AS: 02 IRRIGATION :
 SW SE : Was a chemical/bacteriological sample submitted to department? No ;
 / \ : If yes, mo/day/yr sample was submitted Water well disinfected? Yes :

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 519 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 356 ft. to 516 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 519 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	05 SAND			
2	55	07 FINE SAND 04 SANDY CLAY 31 CALICHE			
55	113	05 SAND 13 FINE GRAVEL			
113	120	04 SANDY CLAY			
120	148	04 SANDY CLAY 07 FINE SAND			
148	165	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
165	200	04 SANDY CLAY 07 FINE SAND			
200	205	07 FINE SAND 08 MEDIUM SAND			
205	251	04 SANDY CLAY 05 SAND			
251	266	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 01/23/97 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/31/97
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 095 STEVENS : NE 1/4 NE 1/4 NW 1/4 : 04 : T 34 S : R 38 W

2 WATER WELL OWNER: GREWELL, PAUL
RR#, St. Address, Box #: ROUTE 1, BOX 107E Board of Agriculture, Division of Water Resources
City, State, ZIP code : HUGOTON, KS 67951- Application Number: 42,338

FROM	TO	LITHOLOGIC LOG
266	298	01 CLAY
298	354	04 SANDY CLAY 07 FINE SAND
354	376	07 FINE SAND 08 MEDIUM SAND 01 CLAY
376	422	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY
422	450	05 SAND 13 FINE GRAVEL 01 CLAY
450	461	04 SANDY CLAY
461	513	05 SAND 13 FINE GRAVEL
513	557	04 SANDY CLAY
557	600	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) 01/23/97 and this record is true to the best of my knowledge and belief, Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/31/97
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Reichert