

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 095 STEVENS | SE 1/4 SE 1/4 SE 1/4 | 15 | T 34 S | R 38 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 6 MILES SOUTH, & 4 MILES WEST OF HUGOTON

2 WATER WELL OWNER: GREWELL, PAUL
 RR#, St. Address, Box #: ROUTE 1, BOX 107E Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 41,463

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 570 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 200 ft. below land surface measured on mo/day/yr 03/29/95
 Pump test data: Well water was 224 ft. after 4 hours pumping 1700 gpm

Estimated Yield 1700 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 570 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 570 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .25
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 263 ft. to 293 ft., From 447 ft. to 567 ft.
 From 340 ft. to 420 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 570 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	05 SAND			
1	13	03 SILTY CLAY			
13	22	07 FINE SAND			
22	32	04 SANDY CLAY			
32	40	04 SANDY CLAY 07 FINE SAND			
40	62	07 FINE SAND 04 SANDY CLAY			
62	103	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
103	125	01 CLAY 04 SANDY CLAY			
125	149	01 CLAY 04 SANDY CLAY			
149	159	04 SANDY CLAY 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 03/28/95 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/18/95
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	SE 1/4 SE 1/4 SE 1/4	15	T 34 S	R 38 W

2 WATER WELL OWNER:	GREWELL, PAUL	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	ROUTE 1, BOX 107E	Application Number: 41,463
City, State, ZIP code :	HUGOTON, KS 67951-	

FROM	TO	LITHOLOGIC LOG
159	177	01 CLAY 04 SANDY CLAY
177	189	04 SANDY CLAY 07 FINE SAND
189	195	01 CLAY
195	226	07 FINE SAND 09 COARSE SAND 01 CLAY
226	247	01 CLAY 04 SANDY CLAY
247	262	04 SANDY CLAY 07 FINE SAND
262	294	05 SAND 28 ROCK 13 FINE GRAVEL
294	308	04 SANDY CLAY 05 SAND
308	339	04 SANDY CLAY 01 CLAY
339	387	05 SAND 28 ROCK 13 FINE GRAVEL
387	415	17 SAND & GRAVL 28 ROCK 04 SANDY CLAY
415	421	05 SAND 28 ROCK 13 FINE GRAVEL
421	445	04 SANDY CLAY 05 SAND
445	456	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
456	501	05 SAND 28 ROCK 13 FINE GRAVEL
501	522	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
522	541	07 FINE SAND 09 COARSE SAND 01 CLAY
541	567	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
567	584	31 CALICHE 19 SHALE
584	620	19 SHALE 31 CALICHE 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/28/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/18/95 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bruce J. Reichmann*