

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: STEVENS SW 1/4 NE 1/4 SE 1/4 10 T 34 S R 39 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM ROLLA, KS. - 3/4 S., 5 E. AND 3/4 MILES SOUTH

2 WATER WELL OWNER: HIGGINS, JACK  
 RR#, St. Address, Box #: BOX 285  
 City, State, ZIP code: ROLLA, KS 67954- Board of Agriculture, Division of Water Resources  
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NW	NE
2	SW	SE

4 DEPTH OF COMPLETED WELL 180 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 120 ft. below land surface measured on mo/day/yr 09/08/94  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 180 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 180 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 180 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 180 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE - NEW SITE  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	TOPSOIL FINE SAND			
10	55	FINE SAND CLAY			
55	64	MEDIUM GRAVEL			
64	130	BROWN CLAY CALACHIE			
130	142	BROWN CLAY			
142	160	FINE - MED SAND			
160	175	MEDIUM SAND SMALL GRAVEL			
175	300	RED BED BROWN CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/08/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/10/94 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*