

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: MORTON NW 1/4 NW 1/4 SW 1/4 28 T 34 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM ELKHART, KS. 6 MILES NORTHEAST AND 1/2 MILE SOUTH

2 WATER WELL OWNER: BARNES, BILL
 RE#, St. Address, Box #: BOX 121
 City, State, ZIP code: ELKHART, KS 67950- Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	NE	SE
2	EW	SW
3	NE	SE
4	EW	SW

4 DEPTH OF COMPLETED WELL 290 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 131 ft. below land surface measured on mo/day/yr 01/23/95
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 290 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 290 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 235 ft. to 275 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 290 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTHWEST How many feet? 60

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	TOPSOIL FINE SAND			
10	20	CLAY			
20	37	SAND GRAVEL CLAY			
37	60	CLAY			
60	70	SAND			
70	100	FINE - MED SAND SAND			
100	225	CLAY			
225	275	FINE - MED SAND SAND			
275	290	RED BED			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/23/95 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 02/07/95
 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*