


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Morton	NW 1/4 SE 1/4 SE 1/4	23	T 34 S	R 41 E/W

Distance and direction from nearest town or city street address of well if located within city?

Wilborton Jct 56 & Rd. 16, 1 6/10 NE., on 56, 1/2S., thru 2 gates, 1/4 SE

2 WATER WELL OWNER:	Oxy Usa Inc.	Tucker B-2
RR#, St. Address, Box #	P.O. Box 2528	Board of Agriculture, Division of Water Resources
City, State, ZIP Code	Liberal, Ks 67905 - 2528	Application Number: 960403

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 305 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. 175 ft. 2. 175 ft. 3. 11-07-96 ft.
	WELL'S STATIC WATER LEVEL 175 ft. below land surface measured on mo/day/yr 11-07-96
	Pump test data: Well water was 231 ft. after 1 hours pumping 95 gpm
	Est. Yield 95 gpm: Well water was 231 ft. after 1 hours pumping 95 gpm
	Bore Hole Diameter 9 1/2 in. to 305 ft., and 305 in. to 305 ft.
	WELL WATER TO BE USED AS:
	1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
	2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well
	Was a chemical/bacteriological sample submitted to Department? Yes X No X If yes, mo/day/yr sample was submitted
	Water Well Disinfected? Yes X No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter 5 in. to 300 ft., Dia			11 Other (specify)
Casing height above land surface 24 in., weight 2.902 lbs./ft. Wall thickness or gauge No. 280 SDR 21			12 None used (open hole)
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
3 Torch cut			10 Other (specify)
SCREEN-PERFORATED INTERVALS:	From 240 ft. to 300 ft.	From 240 ft. to 300 ft.	From 240 ft. to 300 ft.
GRAVEL PACK INTERVALS:	From 140 ft. to 305 ft.	From 140 ft. to 305 ft.	From 140 ft. to 305 ft.

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other Hole Plug
Grout Intervals:	From 0 ft. to 16 ft.	From 0 ft. to 16 ft.	From 0 ft. to 16 ft.	From 0 ft. to 16 ft.
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? Northeast			How many feet? 200	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Surface			
2	28	Sandy Clay			
28	49	Sand			
49	148	Clay & Sandy Clay			
148	167	Sand			
167	188	Clay			
188	206	Sand			
206	240	Clay			
240	262	Sand			
262	266	Clay			
266	298	Sand			
298	305	Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11-07-96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. KWCL - 430 This Water Well Record was completed on (mo/day/yr) 11-07-96 under the business name of Howard Drlg. Box 806, Beaver, Ok 73932 by (signature) Howard Drlg.
--