

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: NORTON SW 1/4 SW 1/4 SE 1/4 6 T 34 S R 42 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM BLKHART ON HIGHWAY 27 - 7 1/2 N, 2 W TO MIDDLE SPRINGS

2 WATER WELL OWNER: U.S. FOREST SERVICE  
 ER#, St. Address, Box #: BOX 300 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: BLKHART, KS 67950- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

NW NE SW SE X	4 DEPTH OF COMPLETED WELL 90 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. WELL'S STATIC WATER LEVEL 10 ft. below land surface measured on 06/24/96 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 10 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 10 in. to 90 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No; If yes, no/day/yr sample was submitted Water well disinfected? Yes
---------------------------	---

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOUED  
 Blank casing diameter 6 in. to 90 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 40 ft. to 60 ft., From 0 ft. to 0 ft.  
 From 80 ft. to 90 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 90 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: OUT HOUSE  
 Direction from well: SOUTHWEST How many feet? 120

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL SANDSTONE			
20	55	SANDSTONE			
55	75	SHALE - Red			
75	90	SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 06/24/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 07/01/96 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Joseph Crist*

P.S. - The last 22 ft of casing is .250 steel.