

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Morton

Location listed as:

Section-Township-Range: 33-42S-34WFraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): NE SE SE

Location changed to:

33-34S-42WNE SE SEOther changes: Initial statements: From Elkhart - North on 27, 3 miles East
on Road 1.Changed to: From Elkhart: 2 mi. N. on Hwy. 27, 1 mi. E.,
 $\frac{1}{4}$ mi. N.

Comments: _____

verification method: Legal & written descriptions, position on plat map,
and Elkhart North 1:24,000 topo. map.initials: DR date: 7/20/2005submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: MORTON NE 1/4 SE 1/4 SE 1/4 33 T 42 S R 34 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM BLKHART - NORTH ON 27, 3 MILES EAST ON ROAD 1

2 WATER WELL OWNER: CIMARRON NATIONAL GRASS
 RR#, St. Address, Box #: PO BOX 300 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: BLKHART, KS 67950- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
2	---		---		---
3	---		---		---
4	---		---		---
5	---		---		---
6	---		---		---
7	---		---		---
8	---		---		---

4 DEPTH OF COMPLETED WELL 265 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 122 ft. below land surface measured on no/day/yr 04/05/05
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 265 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 265 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 180 ft. to 200 ft., From 0 ft. to 0 ft.
 From 220 ft. to 260 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 265 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTH How many feet? 25

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 35 CALACHIE			
20	40	35 CALACHIE 37 FIN-COAR SAN			
40	80	37 FIN-COAR SAN 38 SMAL-MED GRA 05 CLAY			
80	100	05 CLAY 37 FIN-COAR SAN 05 CLAY			
100	120	05 CLAY 37 FIN-COAR SAN 05 CLAY			
120	140	37 FIN-COAR SAN			
140	160	10 FINE-MEDSAND 05 CLAY 19 LAYERS			
160	180	05 CLAY 02 FINE SAND 19 LAYERS			
180	200	37 FIN-COAR SAN 26 RED CLAY 32 TAN CLAY			
200	220	26 RED CLAY 29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 04/06/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 05/06/05 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Insid Creek*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: MORTON	NE 1/4 SE 1/4 SE 1/4	33	T 42 S	R 34 W

2 WATER WELL OWNER: CIMARRON NATIONAL GRASS

RR#, St. Address, Box #: PO BOX 300

City, State, ZIP code: ELKHART, KS 67950-

Board of Agriculture, Division of Water Resources

Application Number:

FROM	TO	LITHOLOGIC LOG
220	250	29 SANDSTONE
250	265	RED 31 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/06/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/06/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Insid Creek*