

1 LOCATION OF WATER WELL: COUNTY: 065 MORTON FRACTION SE 1/4 NW 1/4 SE 1/4 SECTION NUMBER 08 TOWNSHIP NUMBER T 34 RANGE NUMBER R 43 W

DISTANCE AND DIRECTION FROM NEAREST TOWN OR CITY STREET ADDRESS OF WELL IF LOCATED WITHIN CITY?  
FROM ELKHART; APPX 5 1/2 MILES WEST & 6 MILES NORTH

2 WATER WELL OWNER: ANADARKO PETROLEUM RR#, ST. ADDRESS, Box #: 701 S. TAYLOR ST STE 400 BOARD OF AGRICULTURE, DIVISION OF WATER RESOURCES

CITY, STATE, ZIP CODE : AMARILLO, TX 79101-2424 APPLICATION NUMBER:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
W	NW	NE	E
SW	X SE		

4 DEPTH OF COMPLETED WELL 235 ELEVATION: 0  
DEPTH(S) GROUNDWATER ENCOUNTERED 1. 0 FT. 2. 0 FT. 3. 0 FT.

WELL'S STATIC WATER LEVEL 125 FT. BELOW LAND SURFACE MEASURED ON MO/DAY/YR 4/2/03  
PUMP TESTDATA: WELL WATER WAS 0 FT. AFTER 0 HOURS PUMPING 0 GPM

ESTIMATED YIELD 0 GPM: WELL WATER WAS 0 FT. AFTER 0 HOURS PUMPING 0 GPM

BORE HOLE DIAMETER 7 7/8 IN. TO 240 FT., AND IN. TO 0 FT.

WELL WATER TO BE USED AS: 10 MONITORING

WAS A CHEMICAL/BACTERIOLOGICAL SAMPLE SUBMITTED TO DEPARTMENT? No ;  
If YES, MO/DAY/YR SAMPLE WAS SUBMITTED WATER WELL DISINFECTED? YES

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: THREADED  
BLANK CASING DIAMETER 2 IN. TO 235 FT., DIA IN. TO 0 FT., DIA IN. TO 0 FT.  
CASING HEIGHT ABOVE LAND SURFACE 12 IN., WEIGHT .67 LBS/FT. WALL THICKNESS OR GAUGE NO. .154  
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: FROM 210 FT. TO 230 FT., FROM 0 FT. TO 0 FT.  
FROM 0 FT. TO 0 FT., FROM 0 FT. TO 0 FT.  
GRAVEL PACK INTERVALS: FROM 20 FT. TO 149 FT., FROM 0 FT. TO 0 FT.  
FROM 209 FT. TO 240 FT., FROM 0 FT. TO 0 FT.

6 GROUT MATERIAL 03 BENTONITE  
GROUT INTERVALS: FROM 0 FT. TO 20 FT., FROM 149 FT. TO 209 FT., FROM 0 FT. TO 0 FT.  
WHAT IS THE NEAREST SOURCE OF POSSIBLE CONTAMINATION: NONE OBSERVED  
DIRECTION FROM WELL? HOW MANY FEET? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	16	07 FINE SAND 08 MEDIUM SAND			
16	20	05 SAND			
20	80	03 SILTY CLAY 05 SAND			
80	120	05 SAND			
120	160	03 SILTY CLAY 05 SAND			
160	175	01 CLAY 05 SAND			
175	234	06 VERY FN SAND 01 CLAY			
234	240	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: THIS WATER WELL WAS CONSTRUCTED UNDER MY JURISDICTION AND WAS COMPLETED ON (MO/DAY/YEAR) 04/02/03 AND THIS RECORD IS TRUE TO THE BEST OF MY KNOWLEDGE AND BELIEF. KANSAS WATER WELL CONTRACTOR'S LICENSE No. 145 THIS WATER WELL RECORD WAS COMPLETED ON (MO/DAY/YR) 09/09/03 UNDER THE BUSINESS NAME OF HENKLE DRILLING & SUPPLY BY (SIGNATURE) Bruce Richmond



October 26, 2016

Kenny Sullivan  
Kansas Corporation Commission  
Conservation Division  
210 E. Frontview, Suite A  
Dodge City, KS 67801

Re: Smith B5 SWD Well (Smith Finn Site Project)

On August 23, 2016, Anadarko E&P Onshore LLC and its affiliates (collectively, "Anadarko") entered into a purchase and sale agreement with Merit Hugoton II, LLC, an affiliate of Merit Energy Company ("Merit"). Pursuant to that agreement, Merit has agreed to acquire all of Anadarko's interest in certain upstream and midstream assets in southwest Kansas, northwest Oklahoma and southeast Colorado. Consequently, Anadarko is requesting Kansas Corporation Commission (KCC) to transfer our remediation obligations for the Smith B5 SWD Well (Smith Finn Site) to Merit.

In connection with the acquisition, Merit has agreed to assume responsibility for Anadarko's obligations with respect to the Smith Finn Site located in Morton County, Kansas, regardless of whether such obligations arose prior to or after the acquisition of the assets by Merit. This acquisition includes the assumption of responsibility by Merit for the existing remediation system, associated infrastructure, such as piping, flow meters, pumping wells, and monitoring wells, and permits. A complete list of the Smith Finn Site monitoring and pumping wells is included as Attachment 1 for reference.

Merit will be submitting a Form T-1 to KCC in support of their request for a change in operator for the Smith B5 SWD well injection permit (# D-0770). Anadarko and Merit will also be working with the Kansas Department of Agriculture to transfer Anadarko's water appropriation Term Permit (File No. 20099078), which is necessary to operate the groundwater extraction wells, to Merit.

Please be advised that Anadarko further requests the refund of any regulatory oversight deposit that remains once this transfer is complete. The sale to Merit, and the assumption of such obligations by Merit, is expected to occur on October 31, 2016. Merit's contact information is as follows:

RECEIVED  
OCT 27 2016  
BUREAU OF WATER

Merit Hugoton II, LLC  
13727 Noel Road, Suite 1200  
Tower 2  
Dallas, Texas 75240  
Facsimile: (972) 960-1252  
Attn: Mark Savoy

If you have any questions or comments you can contact me at (832) 636-2879.

Sincerely,

A handwritten signature in black ink, appearing to read "Greg Feege". The signature is fluid and cursive, with the first name "Greg" and last name "Feege" clearly distinguishable.

Greg Feege, P.E.  
Anadarko Petroleum Corp

cc: Mark Savoy, Merit Energy  
Pam Chaffee, Kansas Department of Health and Environment

Attachment 1: Smith Finn Site Well List

# Attachment 1.

## Smith Finn Well List

Inventory of Wells Originally Installed by Anadarko Petroleum in support of remediation at the Smith Finn Site

Well ID	Well Type	Installation Date	GPS Location		County	Ownership Status, Effective Oct. 31, 2016
			Latitude (degrees north)	Longitude (degrees west)		
PW-1	Pumping	4/3/2006	37.09802	-102.01149	Morton	Merit Energy
PW-2	Pumping	4/4/2006	37.09958	-102.01255	Morton	Merit Energy
PW-3	Pumping	7/20/2009	37.10047	-102.01477	Morton	Merit Energy
PW-4	Pumping	6/5/2012	37.09830	-102.01182	Morton	Merit Energy
MW10-8	Monitoring	3/26/2003	37.10212	-102.01354	Morton	Merit Energy
MW11-8	Monitoring	3/17/2003	37.10213	-102.01375	Morton	Merit Energy
MW12-8	Monitoring	3/15/2003	37.10196	-102.01367	Morton	Merit Energy
MW13-8	Monitoring	3/29/2003	37.09848	-102.01200	Morton	Merit Energy
MW14-8	Monitoring	3/28/2003	37.09849	-102.01184	Morton	Merit Energy
MW15-8	Monitoring	3/27/2003	37.09835	-102.01185	Morton	Merit Energy
MW16-8	Monitoring	8/17/2005	37.09769	-102.01104	Morton	Merit Energy
MW17-8	Monitoring	8/18/2005	37.09762	-102.01098	Morton	Merit Energy
MW18-8	Monitoring	8/18/2005	37.09768	-102.01092	Morton	Merit Energy

RECEIVED

OCT 27 2013

BUREAU OF WATER