

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: MORTON		Fraction SE 1/4 NW 1/4 NW 1/4		Section Number 10	Township Number T 34 S	Range Number R 43 W
Distance and direction from nearest town or city street address of well if located within city? FROM ELKHART, KS. - 8 W. ON HIGHWAY 27, 4W, 11/2 W AND 1/4 W						
2 WATER WELL OWNER: MORTON CO. GRAZING ASSN. RR#, St. Address, Box #: BOX 121 City, State, ZIP code: ELKHART, KS 67950-		<i>Well #1</i> Board of Agriculture, Division of Water Resources Application Number:				
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 140 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.				
<div style="text-align: center;"> </div>		WELL'S STATIC WATER LEVEL 74 ft. below land surface measured on mo/day/yr 08/25/94 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 9 in. to 140 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No; If yes, mo/day/yr sample was submitted Water well disinfected? Yes				
5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED Blank casing diameter 5 in. to 140 ft., Dia in. to 0 ft., Dia in. to 0 ft. Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC SCREEN OR PERFORATION OPENINGS ARE: SAW CUT						
SCREEN PERFORATED INTERVALS: From 95 ft. to 135 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 20 ft. to 140 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.						
6 GROUT MATERIAL BENTONITE Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft. What is the nearest source of possible contamination: NONE - NEW SITE Direction from well? How many feet? 0						
FROM	TO	LITHOLOGIC LOG		FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY				
20	55	FINE - MED SAND				
55	74	BROWN CLAY				
74	80	MEDIUM SAND CLAY				
80	118	YELLOW CLAY SAND IN LAYERS				
118	120	CLAY SAND				
120	130	MEDIUM SAND SMALL GRAVEL				
130	140	RED BED				
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/25/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/16/94 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Justin E. Creek</i>						