

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well: County <u>Seward</u>		Fraction <u>NE 1/4 NE 1/4 NE 1/4</u>		Section number <u>14</u>		Township number <u>T 35 S</u>		Range number <u>R 34 E/W</u>			
2. Distance and direction from nearest town or city: <u>4 mi SW of Liberal on 54</u>				3. Owner of well: <u>Mrs. FE Mead</u>							
Street address of well location if in city:				R.R. or street: <u>RFD #1</u>							
				City, state, zip code: <u>Liberal Kansas 67901</u>							
4. Locate with "X" in section below:				Sketch map:				6. Bore hole dia. <u>8 3/4</u> in. Completion date <u>12-19-77</u>			
								Well depth <u>250</u> ft.			
								7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug			
								<input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
								8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry			
								<input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock			
								<input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
5. Type and color of material				From		To		9. Casing: Material <u>PVC</u> Height: Above or below			
<u>Top Soil</u>				<u>0</u>		<u>2</u>		Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>12"</u> in.			
<u>Fine Sand</u>				<u>2</u>		<u>15</u>		RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <u> </u> lbs./ft.			
<u>Clay with fine sand</u>				<u>15</u>		<u>98</u>		Dia. <u>5</u> in. to <u>250</u> ft. depth Wall Thickness: inches			
<u>Med Sand</u>				<u>98</u>		<u>109</u>		Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>258</u>			
<u>Light Clay</u>				<u>109</u>		<u>210</u>		10. Screen: Manufacturer's name <u>Hand Sawn</u>			
<u>Coarse Sand</u>				<u>210</u>		<u>250</u>		Type <u>Slot</u> Dia. <u>5/16"</u>			
								Slot/gauze <u>1/4"</u> Length <u>3"</u>			
								Set between <u>210</u> ft. and <u>250</u> ft.			
								Gravel pack? <u>Yes</u> Size range of material <u>4-8</u>			
								11. Static water level: <u>135</u> ft. below land surface Date <u>12-19-77</u>			
								12. Pumping level below land surfaces:			
								____ ft. after ____ hrs. pumping <u>NA</u> g.p.m.			
								____ ft. after ____ hrs. pumping ____ g.p.m.			
								Estimated maximum yield ____ g.p.m.			
								13. Water sample submitted: ____ mo./day/yr.			
								Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Date ____			
								14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <u>Pitless</u> inches above grade			
								15. Well grouted? <u>Yes</u>			
								With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete			
								Depth: From <u>4</u> ft. to <u>14</u> ft.			
								16. Nearest source of possible contamination: ft. <u>65</u> Direction <u>NW</u> Type <u>SEWER</u>			
								Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
								17. Pump: Not installed			
								Manufacturer's name <u>Fairbanks</u>			
								Model number ____ HP <u>1</u> Volts <u>230</u>			
								Length of drop pipe <u>160</u> ft. capacity <u>10</u> g.p.m.			
								Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine			
								<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating			
								<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
								20. Water well contractor's certification:			
								This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.			
								<u>Combs End 342</u>			
								Business name <u>Terpin, Okla</u> License No. ____			
								Address <u>77 Neal Road</u>			
								Signed <u> </u> Date <u>1-8-78</u>			
								Authorized representative			
18. Elevation:		19. Remarks:									
Topography:											
<input type="checkbox"/> Hill											
<input checked="" type="checkbox"/> Slope											
<input type="checkbox"/> Upland											
<input type="checkbox"/> Valley											

T 35 S R 34 E
 Sec 14 NE NE 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5