

1 LOCATION OF WATER WELL: COUNTY: 095 STEVENS	Fraction SW 1/4 SW 1/4 NW 1/4	Section Number 15	Township Number T 35 S	Range Number R 35 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM WOODS; APPX 11 MILES SOUTH & 3/4 MILE WEST

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :	R & H ROSENBLAD TRUST PO BOX 1041 ULYSSES, KS 67880-1041	Board of Agriculture, Division of Water Resources Application Number: 15,923
---	--	---

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 385 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 165 ft. below land surface measured on mo/day/yr 04/17/06
Pump test data: Well water was 288 ft. after 4 hours pumping 1100 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 385 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 385 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 232 ft. to 332 ft.,	From 0 ft. to 0 ft.
	From 345 ft. to 365 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 385 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? SOUTHWEST How many feet? 110

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT 05 SAND			
3	8	04 SANDY CLAY 31 CALICHE			
8	16	07 FINE SAND			
16	29	01 CLAY			
29	62	07 FINE SAND 01 CLAY			
62	90	01 CLAY 05 SAND			
90	160	01 CLAY 20 LIMESTONE			
160	196	01 CLAY 20 LIMESTONE			
196	221	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
221	233	01 CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/12/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	SW 1/4 SW 1/4 NW 1/4	15	T 35 S	R 35 W

2 WATER WELL OWNER: R & H ROSENBLAD TRUST
RR#, St. Address, Box # : PO BOX 1041
City, State, ZIP code : ULYSSES, KS 67880-1041

Board of Agriculture, Division of Water Resources
Application Number: 15,923

FROM	TO	LITHOLOGIC LOG
233	253	07 FINE SAND 01 CLAY
253	260	01 CLAY
260	270	01 CLAY 05 SAND
270	280	07 FINE SAND
280	332	07 FINE SAND 08 MEDIUM SAND 01 CLAY
332	343	01 CLAY
343	365	06 VERY FN SAND 07 FINE SAND 01 CLAY
365	375	01 CLAY 20 LIMESTONE
375	386	20 LIMESTONE
386	406	01 CLAY 20 LIMESTONE
406	414	06 VERY FN SAND 07 FINE SAND
414	446	01 CLAY 20 LIMESTONE
446	460	01 CLAY 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/12/06 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145
under the business name of HENKLE DRILLING & SUPPLY

This Water Well Record was completed on (mo/day/yr) 07/03/06
by (signature) *Bruce J. Reichman*