

Elite Irrigation & Drilling Inc

Po box 1318 Liberal, KS 67905

Test Hole Drilling Log

Customer: Mills Farms - Matt Mills

1902 Road C

Hugoton, KS 67951

County: Stevens

Quarter: SW NW NW Section: 5 Township: 35 Range: 36

GPS Location: 37.0372662° -101.2656125°

Total Pay: 86' Total Depth: 660'

Date: 06/03/2018

Phone: -

E-Logg: no Test #: 1

Driller: Tyler

Description of Strata from the surface down.

(example: 3-50, 47. Sand; Footage is from 3-50 feet, pay = 47. Sand is the strata description.)

0-7. Top soil

7-11. Clay fine sand mix

11-30. Fine sand

30-71. Clay

71-82. Sand fine to medium

82-94. Clay Sand mix

94-113. Sand

113-132. Sand clay mix

132-175. Clay

175-252. Sand clay mix sand stone streaks

252-277. Medium sand to coarse

277-352. Clay

352-394. Blue shale

394-542. Blue shale brown clay mix

542-555, 13. Fine to medium sand

555-628, 73. Medium to coarse Little clay streaks

628-647. Coarse sand gravel mix (rock shelf)

647-660. Red bed