

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SE 1/4 SW 1/4 SW 1/4 17 T 35 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 12 MILES SOUTH & 1/2 MILE WEST OF HUGOTON

2 WATER WELL OWNER: GREWELL, PAUL
 RR#, St. Address, Box #: ROUTE 1, BOX 107E Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 355 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 180 ft. below land surface measured on mo/day/yr 08/14/95
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 11 in. to 355 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 6 in. to 355 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. 3/16
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 215 ft. to 295 ft., From 0 ft. to 0 ft.
 From 335 ft. to 355 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 355 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 32

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	9	01 CLAY			
9	13	07 FINE SAND			
13	22	01 CLAY			
22	31	01 CLAY 31 CALICHE 07 FINE SAND			
31	41	04 SANDY CLAY 20 LIMESTONE			
41	45	07 FINE SAND			
45	67	01 CLAY 05 SAND			
67	85	07 FINE SAND 01 CLAY 05 SAND			
85	117	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/17/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/01/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 095 STEVENS : SE 1/4 SW 1/4 SW 1/4 : 17 : T 35 S : R 37 W

2 WATER WELL OWNER: GREWELL, PAUL
RR#, St. Address, Box #: ROUTE 1, BOX 107E Board of Agriculture, Division of Water Resources
City, State, ZIP code : HUGOTON, KS 67951- Application Number:

FROM	TO	LITHOLOGIC LOG
117	135	20 LIMESTONE
135	145	04 SANDY CLAY 20 LIMESTONE
145	168	01 CLAY 20 LIMESTONE
168	181	04 SANDY CLAY
181	215	07 FINE SAND 09 COARSE SAND 01 CLAY
215	240	05 SAND 13 FINE GRAVEL 01 CLAY
240	288	05 SAND 13 FINE GRAVEL 15 CRS GRAVEL
288	320	01 CLAY 20 LIMESTONE 07 FINE SAND
320	353	07 FINE SAND 08 MEDIUM SAND 01 CLAY
353	382	01 CLAY 20 LIMESTONE 07 FINE SAND
382	500	CLAY 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) 08/17/95 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/01/95
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruno J. Reichmuth*