

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 095 STEVENS SE 1/4 SE 1/4 SW 1/4 05 T 35 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 10 MILES SOUTH & 3/4 WEST OF HUGOTON

2 WATER WELL OWNER: WILLIS, MIKE
 RR#, St. Address, Box #: HC 01, BOX 3 D Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 42,230

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 659 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 157 ft. below land surface measured on mo/day/yr 11/08/96
 Pump test data: Well water was 182 ft. after 4 hours pumping 1700 gpm
 Estimated Yield 1700 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 659 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 659 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 316 ft. to 656 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 659 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	220	01 CLAY 05 SAND			
220	240	08 MEDIUM SAND 09 COARSE SAND 04 SANDY CLAY			
240	260	04 SANDY CLAY 07 FINE SAND 09 COARSE SAND			
260	380	08 MEDIUM SAND 09 COARSE SAND			
380	400	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			
400	440	08 MEDIUM SAND 09 COARSE SAND			
440	560	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			
560	580	01 CLAY 07 FINE SAND 08 MEDIUM SAND			
580	600	05 SAND 01 CLAY			
600	620	08 MEDIUM SAND 09 COARSE SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/06/96 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/22/96
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 095 STEVENS : SE 1/4 SE 1/4 SW 1/4 : 05 : T 35 S : R 37 W

2 WATER WELL OWNER: WILLIS, MIKE
RR#, St. Address, Box # : HC 01, BOX 3 D Board of Agriculture, Division of Water Resources
City, State, ZIP code : HUGOTON, KS 67951- Application Number: 42,230

FROM	TO	LITHOLOGIC LOG
620	640	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL
640	660	05 SAND 13 FINE GRAVEL 01 CLAY
660	680	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/06/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/22/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Richmond