

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	NE 1/4 NE 1/4 NW 1/4	10	T 35 S	R 37 W

Distance and direction from nearest town or city street address of well if located within city?  
FROM HUGOTON; APPX 10 MILES SOUTH

2 WATER WELL OWNER: S & G MANAGEMENT TRUST  
RR#, St. Address, Box #: 9210 VILLAGE DRIVE Board of Agriculture, Division of Water Resources  
City, State, ZIP code: SAN ANTONIO, TX 78217-3425 Application Number: 45,763

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

/ \			X		
1	---	NW	---	NE	---
M	W				E
i					
l					
e					
		SW		SE	
\ /					

4 DEPTH OF COMPLETED WELL 663 BLEVEATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 179 ft. below land surface measured on mo/day/yr 10/01/04  
Pump test data: Well water was 331 ft. after 4 hours pumping 1600 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 663 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
Blank casing diameter 16 in. to 663 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 538 ft. to 658 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 663 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: NONE OBSERVED  
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	10	04 SANDY CLAY			
10	16	01 CLAY			
16	25	04 SANDY CLAY 07 FINE SAND			
25	40	07 FINE SAND			
40	55	07 FINE SAND 04 SANDY CLAY			
55	64	05 SAND 04 SANDY CLAY			
64	78	04 SANDY CLAY 20 LIMESTONE 05 SAND			
78	83	07 FINE SAND			
83	192	04 SANDY CLAY 07 FINE SAND 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/29/04 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/04/04  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	NE 1/4 NE 1/4 NW 1/4	10	T 35 S	R 37 W

2 WATER WELL OWNER: S & G MANAGEMENT TRUST  
RR#, St. Address, Box # : 9210 VILLAGE DRIVE  
City, State, ZIP code : SAN ANTONIO, TX 78217-3425

Board of Agriculture, Division of Water Resources  
Application Number: 45,763

FROM	TO	LITHOLOGIC LOG
192	231	07 FINE SAND 08 MEDIUM SAND 01 CLAY
231	262	07 FINE SAND 01 CLAY
262	286	04 SANDY CLAY 05 SAND
286	297	07 FINE SAND 01 CLAY
297	378	04 SANDY CLAY 05 SAND
378	534	01 CLAY
534	600	01 CLAY 05 SAND
600	625	05 SAND 01 CLAY 13 FINE GRAVEL
625	658	05 SAND 13 FINE GRAVEL 28 ROCK
658	665	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/29/04 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/04/04  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

