

1 LOCATION OF WATER WELL: COUNTY: 095 STEVENS	Fraction SE 1/4 SW 1/4 SW 1/4	Section Number 17	Township Number T 35 S	Range Number R 37 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HUGOTON; APPX 12 MILES SOUTH & 3/4 MILE WEST

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :	PAUL GREWELL RT 1 BOX 107E HUGOTON, KS 67951-9616	Board of Agriculture, Division of Water Resources Application Number:
---	---	--

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 390 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 215 ft. below land surface measured on mo/day/yr 08/22/05
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 5/8 in. to 390 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC	CASING JOINTS: OTHER CASING JNT - CERTI LOCK
Blank casing diameter 6 in. to 390 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316	
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC	
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT	

SCREEN PERFORATED INTERVALS:	From 250 ft. to 290 ft., From 0 ft. to 0 ft.
	From 350 ft. to 370 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 390 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? SOUTH How many feet? 15

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	173	04 SANDY CLAY 07 FINE SAND 20 LIMESTONE			
173	200	05 SAND 01 CLAY			
200	216	05 SAND			
216	247	04 SANDY CLAY 05 SAND			
247	253	05 SAND 13 FINE GRAVEL			
253	269	04 SANDY CLAY 05 SAND			
269	281	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
281	288	04 SANDY CLAY			
288	310	04 SANDY CLAY 07 FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/16/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/13/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 095 STEVENS	SW 1/4 SE 1/4 SW 1/4	17	T 35 S	R 37 W

2 WATER WELL OWNER:	PAUL GREWELL	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT 1 BOX 107E	Application Number:
City, State, ZIP code :	HUGOTON, KS 67951-9616	

FROM	TO	LITHOLOGIC LOG
310	348	04 SANDY CLAY 05 SAND
348	367	07 FINE SAND 08 MEDIUM SAND 01 CLAY
367	377	01 CLAY
377	400	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/16/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/13/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Ruckmeyer*