

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 095 STEVENS | SE 1/4 SE 1/4 SE 1/4 | 02 | T 35 S | R 38 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 8 3/4 MILES SOUTH & 4 MILES WEST OF FETERITA

2 WATER WELL OWNER: GREWELL, PAUL
 RR#, St. Address, Box #: ROUTE 1, BOX 107E Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUGOTON, KS 67951- Application Number: 42,337

3 LOCATE WELL'S LOCATION WITH | 4 DEPTH OF COMPLETED WELL 668 ELEVATION: 0
 AN "X" IN SECTION BOX: | Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELLS STATIC WATER LEVEL 186 ft. below land surface measured on mo/day/yr 01/31/97
 Pump test data: Well water was 232 ft. after 4 hours pumping 1525 gpm
 Estimated Yield 1525 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 668 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 668 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT
 SCREEN PERFORATED INTERVALS: From 271 ft. to 361 ft., From 437 ft. to 477 ft.
 From 380 ft. to 400 ft., From 555 ft. to 665 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 668 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	14	02 SILT 01 CLAY			
14	16	07 FINE SAND			
16	32	04 SANDY CLAY 07 FINE SAND			
32	60	01 CLAY 31 CALICHE			
60	82	07 FINE SAND 01 CLAY			
82	132	04 SANDY CLAY 31 CALICHE			
132	147	01 CLAY 07 FINE SAND			
147	190	01 CLAY 31 CALICHE			
190	196	07 FINE SAND 08 MEDIUM SAND			
196	201	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 01/29/97 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/06/97
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 095 STEVENS | SE 1/4 SE 1/4 SE 1/4 | 02 | T 35 S | R 38 W

2 WATER WELL OWNER: GREWELL, PAUL
RR#, St. Address, Box #: ROUTE 1, BOX 107E Board of Agriculture, Division of Water Resources
City, State, ZIP code: HUGOTON, KS 67951- Application Number: 42,337

FROM	TO	LITHOLOGIC LOG
201	213	08 MEDIUM SAND 01 CLAY
213	225	01 CLAY
225	229	07 FINE SAND
229	252	08 MEDIUM SAND 01 CLAY
252	271	04 SANDY CLAY
271	314	08 MEDIUM SAND 07 FINE SAND
314	317	04 SANDY CLAY
317	325	08 MEDIUM SAND
325	328	04 SANDY CLAY
328	361	07 FINE SAND 08 MEDIUM SAND 01 CLAY
361	377	04 SANDY CLAY
377	402	07 FINE SAND 08 MEDIUM SAND 01 CLAY
402	438	01 CLAY
438	444	08 MEDIUM SAND
444	476	08 MEDIUM SAND 07 FINE SAND 01 CLAY
476	492	01 CLAY
492	554	01 CLAY
554	625	05 SAND 01 CLAY 11 GRAVEL
625	631	01 CLAY
631	650	08 MEDIUM SAND 09 COARSE SAND 01 CLAY
650	665	05 SAND 11 GRAVEL 01 CLAY
665	675	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/29/97 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/06/97
under the business name of HENKLE DRILLING & SUPPLY by (signature) 