

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Morton

Location listed as:

Section-Township-Range: 7-40S-35WFraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): SE NE NW

Location changed to:

7-35S-40WSE NE NWOther changes: Initial statements: From Elkhart - E on 156, 2 M on to
Sec. 5. Road & 9 EastChanged to: From Elkhart: 2 mi. NE. on Hwy. 56,
8 $\frac{3}{8}$ mi. E., S. into.

Comments: _____

verification method: Written & legal descriptions, position on plat map,
and Elkhart North, Willburton, & Rolle 1:24,000
topo. maps. initials: DRL date: 7/20/2005

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726

to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: MORTON	SE 1/4 NE 1/4 NW 1/4	7	T 40 S	R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM ELKHART - E ON 156, 2 M ON TO SEC ST. ROAD & 9 EAST

2 WATER WELL OWNER: CINTRON NATIONAL GRASS LAND *Well #2 - Pasture 71*
 RR#, St. Address, Box #: PO BOX 300 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: ELKHART, KS 67950- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 385 ELEVATION: 0																
<table border="1"> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </table>																	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. WELL'S STATIC WATER LEVEL 234 ft. below land surface measured on no/day/yr 04/07/05 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 9 in. to 385 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No; If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 385 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS:	From 320 ft. to 380 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 385 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTHEAST How many feet? 25

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY			
20	80	05 CLAY 02 FINE SAND			
80	100	10 FINE-MEDSAND 05 CLAY 35 CALACHIE			
100	120	32 TAN CLAY			
120	180	32 TAN CLAY 26 RED CLAY			
180	200	32 TAN CLAY 10 FINE-MEDSAND			
200	220	10 FINE-MEDSAND			
220	240	10 FINE-MEDSAND 17 CLAY LAYERS			
240	260	05 CLAY 10 FINE-MEDSAND			
260	280	10 FINE-MEDSAND 32 TAN CLAY			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 04/08/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 05/06/05
 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Clark*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: MORTON	SE 1/4 NE 1/4 NW 1/4	7	T 40 S	R 35 W

2 WATER WELL OWNER: CIMARRON NATIONAL GRASS

RR#, St. Address, Box #: PO BOX 300

City, State, ZIP code: ELKHART, KS 67950-

Board of Agriculture, Division of Water Resources

Application Number:

FROM	TO	LITHOLOGIC LOG
280	300	02 FINE SAND 32 TAN CLAY
300	320	32 TAN CLAY 02 FINE SAND 19 LAYERS
320	340	10 FINE-MEDSAND
340	360	10 FINE-MEDSAND 17 CLAY LAYERS
360	380	10 FINE-MEDSAND 32 TAN CLAY 26 RED CLAY
380	400	26 RED CLAY 41 RED SANDSTON 31 SHALE
400	0	

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/08/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/06/05 under the business name of JOB'S WELL SERVICE, INC.

by (signature) *Justin Creek*