

1/2

*The
Professionals*

MINTER-WILSON DRILLING CO.

INCORPORATED

and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Floyd Penick
Morton Co.
6-14-88

Location: NE $\frac{1}{4}$ 4-35-43
From pivot - $\frac{1}{4}$ So., 1120' E. & 100' No.

Static Water Level - 85'

Test #2

0	1	Top soil
1	11	Fine sand
11	13	Brown clay brown rock - hard strip
13	33	Brown clay
33	41	Fine sand
41	81	Brown sandy clay - white rock mixed
81	89	Fine to medium sand - loose
89	95	Fine to medium sand & gravel - 10% clay
95	110	Fine to medium sand & gravel - streak of coarse gravel - 10% clay
110	116	Medium coarse gravel - tight
116	142	Brown sandy clay - hard spot
142	150	Fine to medium sand & gravel
150	152	Brown clay
152	155	Fine to medium sand & gravel
155	160	Medium coarse gravel
160	173	Brown sandy clay - hard small streak of cemented sand stone
173	175	Red bed