

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

AAB

1. Location of well: County Decatur Fraction NW 1/4 NE 1/4 NE 1/4 Section number 2 Township number T 3 S Range number R 30 BFW

2. Distance and direction from nearest town or city: 7 West Oberlin 3. Owner of well: KFNF
Street address of well location if in city: _____ R.R. or street: _____
City, state, zip code: Oberlin Kans 67749

4. Locate with "X" in section below: Sketch map:
N
W E
S
1 Mile

6. Bore hole dia. 9 in. Completion date 12-10-77
Well depth 160 ft.
7. Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary
8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other
9. Casing: Material P57 Height: Above or below
Threaded Welded Surface 92 in.
RMP PVC Weight _____ lbs./ft.
Dia. 5 in. to 40 ft. depth Wall Thickness: inches or
Dia. _____ in. to _____ ft. depth gage No. 250

5. Type and color of material	From	To
Topsoil	0	36
Soft Limestone	36	44
Clay	44	59
Sand	59	73
Sand & clay	73	84
Clay	84	92
Sandy clay	92	109
Sand	109	120
Sand & clay	120	134
clay	134	145
Sand fair	145	158
Shale	158	160
BROCK 158'		

10. Screen: Manufacturer's name JESS & LOWELL
Type Plastic Dia. 5"
Slot/gauze 1/6 Length 20 ft.
Set between 140 ft. and 160 ft.
ft. and _____ ft.
Gravel pack? Yes Size range of material 1/8 - 3/16
11. Static water level: _____ mo./day/yr.
107 ft. below land surface Date 11-28-77
12. Pumping level below land surfaces: N/A
_____ ft. after _____ hrs. pumping _____ g.p.m.
_____ ft. after _____ hrs. pumping _____ g.p.m.
Estimated maximum yield _____ g.p.m.
13. Water sample submitted: _____ mo./day/yr.
 Yes No Date _____
14. Well head completion:
 Pitless adapter 12 inches above grade
15. Well grouted? Yes
With: Neat cement Bentonite Concrete
Depth: From 50 ft. to 20 ft.
16. Nearest source of possible contamination:
ft. 500 Direction West Type Arroy
Well disinfected upon completion? Yes No
17. Pump:
Manufacturer's name Red Jacket Not installed
Model number _____ HP 3/4 Volts 230
Length of drop pipe 144 ft. capacity 9 g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

18. Elevation: _____
19. Remarks: _____
Topography:
 Hill
 Slope
 Upland
 Valley

20. Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Jelden Drilling 339
Business name _____ License No. _____
Address Jelden Kans
Signed Bob Wagner Date 12-77
Authorized representative

1-3
R
30
W
Sec
1
NW 1/4 NE 1/4