

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well:	County <i>Republic</i>	Fraction <i>SE 1/4 SE 1/4 SW 1/4</i>	Section number <i>29</i>	Township number T <i>3</i> S R	Range number 4 <i>E</i> (W)		
2. Distance and direction from nearest town or city: <i>3.5 of Scandia</i>			3. Owner of well: <i>Alcop Sand Co, Inc</i>				
Street address of well location if in city:			R.R. or street:				
			City, state, zip code: <i>Belleville Mo 66935</i>				
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <i>4.8</i> in. Completion date _____ Well depth <i>42</i> ft. <i>5-20-78</i>			
N W E SW SE S		1 Mile 1 Mile		7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
5. Type and color of material		From		To		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
						9. Casing: Material <i>PVC</i> Height: Above or below Threaded _____ Welded <input checked="" type="checkbox"/> Surface <i>12</i> in. RMP _____ PVC <input checked="" type="checkbox"/> Weight <i>3</i> lbs./ft. Dia. <i>5</i> in. to <i>42</i> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <i>258</i>	
<i>top soil</i>		<i>0</i>		<i>5</i>		10. Screen Manufacturer's name _____ <i>Pumper Supply</i>	
<i>sand</i>		<i>5</i>		<i>14</i>		Type <i>PVC</i> Dia. <i>5</i> Slot/gauge <i>1/16</i> Length <i>10</i> Set between <i>32</i> ft. and <i>42</i> ft. _____ ft. and _____ ft.	
<i>gravel</i>		<i>14</i>		<i>50</i>		Gravel pack? <i>YES</i> Size range of material <i>1/8-1/4</i>	
						11. Static water level: _____ mo./day/yr. <i>8</i> ft. below land surface Date <i>5-20-78</i>	
						12. Pumping level below land surfaces: <i>30</i> ft. after <i>1/2</i> hrs. pumping <i>40</i> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <i>50</i> g.p.m.	
						13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____	
						14. Well head completion: <input type="checkbox"/> Pitless adapter <i>12</i> Inches above grade	
						15. Well grouted? <i>YES</i> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <i>0</i> ft. to <i>10</i> ft.	
						16. Nearest source of possible contamination: <i>NONE</i> ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
						17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
						(Use a second sheet if needed)	
18. Elevation: <i>1421</i>		19. Remarks: <i>well grouted by owner</i>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>361</i> <i>COX-BESWICK IRRIGATION SERVICE</i> Business name _____ License No. _____ Address <i>Clifton Kansas 66933</i> Signed <i>Sharon Cox</i> Date <i>5-27-78</i> Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley				T <i>3</i> S R <i>4</i> E (W) Sec <i>29</i> T <i>36</i> S R <i>4</i> E (W) Sec <i>29</i> T <i>36</i> S R <i>4</i> E (W) Sec <i>29</i>			