


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>Cherokee</u>	Fraction <u>NW 1/4 SE 1/4 NE 1/4</u>	Section number <u>34</u>	Township number <u>T 4</u>	Range number <u>S R 41</u>	
2. Distance and direction from nearest town or city: <u>7500 ft South of St. Francis Southwest</u>			3. Owner of well: <u>Ruben Zweygardt</u> R.R. or street: City, state, zip code: <u>St. Francis Kansas 67756</u>			
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		6. Bore hole dia. <u>8</u> in. Completion date <u>3 June</u> Well depth <u>242</u> ft. <u>82</u>	
5. Type and color of material			From	To	7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
<u>Top soil</u>			<u>0</u>	<u>3</u>	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
<u>Yellow clay</u>			<u>3</u>	<u>41</u>	9. Casing: Material <u>PVC</u> Height: <u>Above or below</u> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <u>2.9</u> lbs./ft. Dia. <u>5</u> in. to <u>242</u> ft. depth; Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth; gage No. <u>20016</u>	
<u>Sand - Gravel - Rock - clay</u>			<u>41</u>	<u>192</u>	10. Screen: Manufacturer's name <u>Crown</u> <u>PLASTIC'S</u> Type <u>5/16"</u> Dia. <u>5"</u> Slot/gauze <u>.20</u> Length <u>10 FT</u> Set between <u>232</u> ft. and <u>242</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/4"</u>	
<u>Sand & Gravel</u>			<u>192</u>	<u>198</u>	11. Static water level: <u>191</u> ft. below land surface Date <u>3 8 82</u> mo./day/yr.	
<u>Sand Rock</u>			<u>198</u>	<u>201</u>	12. Pumping level below land surfaces: <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>10</u> g.p.m.	
<u>Clay with layers of Sand</u>			<u>201</u>	<u>214</u>	13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>	
<u>Rock</u>			<u>214</u>	<u>216</u>	14. Well head completion: <u> </u> Pitless adapter <u>12</u> inches above grade	
<u>Sand & Gravel</u>			<u>216</u>	<u>241</u>	15. Well grouted? <u>yes</u> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>11</u> ft.	
<u>Shale</u>			<u>241</u>	<u>242</u>	16. Nearest source of possible contamination: <u>None</u> ft. <u> </u> Direction <u>PASTURE</u> Type <u>PASTURE</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
					17. Pump: <u>Windmill</u> Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u>210</u> ft. capacity <u>3</u> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input checked="" type="checkbox"/> Other	
(Use a second sheet if needed)						
18. Elevation:	19. Remarks:				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Schuen Burger Drilling</u> Business name <u> </u> License No. <u> </u> Address <u>St. Francis Kansas 67756</u> Signed <u>Richard P. Burger</u> Date <u>6-21-82</u> Authorized representative	
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						