

WATER WELL RECORD					
LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Norton		NE ¼ NE ¼ SW ¼	1	T S R	E/W 26
Distance and direction from nearest town or city street address of well if located within city? 3 W ¾ N New Almelo					
2 WATER WELL OWNER: Raymond Scheetz RR#, St. Address, Box #: H.C.R. 01 Box 60 City, State, ZIP Code: Clayton, Kansas 67629 Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 					
4 DEPTH OF COMPLETED WELL...180 ft. ELEVATION: Depth(s) Groundwater Encountered 1.....ft. 2.....ft. 3.....ft. WELL'S STATIC WATER LEVEL...152 ft. below land surface measured on mo/day/yr .9-17-85 Pump test data: Well water wasft. after hours pumping gpm Est. Yield gpm; Well water was not tested after hours pumping gpm Bore Hole Diameter.....Ø.....in. to ...180 ft., and.....in. toft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes.....No..x..... If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes x No					
5 TYPE OF BLANK CASING USED: Blank casing diameter5 in. to 160 ft., Dia.....in. toft., Dia.....in. toft. Casing height above land surface.....18 in., weight ..1 Ø/10 lbs./ft. Wall thickness or gauge No. SDR 21 TYPE OF SCREEN OR PERFORATION MATERIAL: SCREEN OR PERFORATION OPENINGS ARE: SCREEN-PERFORATED INTERVALS: From....160 ft. to180 ft., From.....ft. to.....ft. GRAVEL PACK INTERVALS: From....18 ft. to180 ft., From.....ft. to.....ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From.....4 ft. to18 ft., From.....ft. to.....ft., From.....ft. to.....ft. What is the nearest source of possible contamination: Direction from well? West How many feet? 200					
LITHOLOGIC LOG FROM TO LITHOLOGIC LOG FROM TO LITHOLOGIC LOG 0 20 top soil 20 75 rock hard soft strips 75 84 sandy clay 84 109 sand 109 147 sand clay 147 171 sand rock and ssnd strips 171 177 sand 177 180 shale					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) .9-17-85 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 139 This Water Well Record was completed on (mo/day/yr) .9-10-85 under the business name of Bartell Drilling by signature Joyce Bartell					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section,, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					