


1 LOCATION OF WATER WELL: County: Decatur	Fraction SW 1/4 NE 1/4 SW 1/4	Section Number 20	Township Number T 5 S	Range Number R 26 E
---	--------------------------------------	--------------------------	------------------------------	----------------------------

Distance and direction from nearest town or city street address of well if located within city?

2 1/2 Miles North of Allison, Ks.

2 WATER WELL OWNER: Frances Bader RR#, St. Address, Box # : Jennings, Ks. 67643 City, State, ZIP Code :	Board of Agriculture, Division of Water Resources Application Number:
---	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL 180 ft. ELEVATION: Depth(s) Groundwater Encountered 1 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 99 ft. below land surface measured on mo/day/yr Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 in. to 180 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No X
---	--

5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) 7 Fiberglass Blank casing diameter 5 in. to 160 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 18 in., weight 2.765 lbs./ft. Wall thickness or gauge No. 258 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 160 ft. to 180 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 180 ft., From ft. to ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage Direction from well? How many feet?
--

LITHOLOGIC LOG			PLUGGING INTERVALS		
FROM	TO		FROM	TO	
0	3	Surface	123	138	Sand w/Clay Sandstone & Caliche Strks.
3	10	Silty Sand			
10	12	Fine Med. Sand	138	143	Med. Sand & Gravel
12	13	Caliche	143	146	Clay
13	35	Fine Sand w/Clay & Caliche Strks.			
35	38	Sandstone	146	148	Fine to Med. Sand & Gravel w/Clay Strks.
38	52	Sandstone Clay & Sand			
52	61	Fine Med. Sand w/Clay & Caliche			
61	90	Fine Med. Sand	148	179	Med. Coarse Sand & Gravel
90	92	Clay	179	182	Sandy Clay
92	95	Fine to Med. Sand	182		Shale
95	99	Clay w/Sand Strks.			
99	102	Fine to Med. Sand & Gravel			
102	110	Tight Fine Sand w/Clay Strks.			
110	123	Clay w/Sand & Caliche Strks.			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-13-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 554 This Water Well Record was completed on (mo/day/yr) 8-16-94 under the business name of Woofter Pump & Well, Inc. by (signature) 