


USE TYPEWRITER OR BALL
POINT/PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

ABB

1 Location of well:	County <u>Rawlins</u>	Township name <u>Maraga</u>	Fraction <u>NW 1/4 NE 1/4</u>	Section number <u>6</u>	Town number <u>5</u>	Range number <u>36</u>
Distance and direction from nearest town or city: <u>12 miles SW of McDonald Ks</u>			3 Owner of well: <u>O A Cooper</u> Address: <u>Hermit Wilke</u> <u>Haldrege, Neb</u>			
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:			4 Well depth: <u>306</u> ft. Date of completion <u>6-3-75</u> Well diameter <u>30</u> in.
2			Type and color of material	From	To	5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
			<u>top soil and clay</u>	<u>0</u>	<u>180</u>	6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well
			<u>6' gravel little clay 4' porous rock</u>	<u>180</u>	<u>190</u>	7 Casing: Material <u>Steel</u> Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. Dig. Weight <u>32</u> lbs./ft. <u>L</u> <u>16</u> in. to <u>306</u> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No in. to ft. depth
			<u>10' porous rock strips of clay & clay</u>	<u>190</u>	<u>200</u>	8 Screen: <u>M.A. Brown Enterprise</u> Manufacturer's name Type <u>free flow</u> Dia. <u>16"</u> Slot/gauze <u>3/16</u> Length <u>40'</u> Set between <u>264</u> ft. and <u>306</u> ft. Fittings: <u>3/4"</u> Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material
			<u>4' porous rock & clay 3' med sand & clay</u>	<u>200</u>	<u>210</u>	9 Static water level: <u>194</u> ft. below land surface Date <u>6-5-75</u>
			<u>7' gravel 3' cemented gravel</u>	<u>210</u>	<u>220</u>	10 Pumping level below land surfaces: <u>290</u> ft. after <u>40</u> hrs. pumping <u>420</u> g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield <u>420</u> g.p.m.
			<u>5' gravel 5' fine sand little clay</u>	<u>220</u>	<u>230</u>	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date
			<u>2' fine sand 8' porous rock</u>	<u>230</u>	<u>240</u>	12 Well head completion: <u>12"</u> <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
			<u>3' porous rock 5' clay 2' fine sand</u>	<u>240</u>	<u>250</u>	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <u>Cuddled</u> <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> clay Depth: From <u>0</u> ft. to <u>10</u> ft.
			<u>7' fine sand 3' sandy clay</u>	<u>250</u>	<u>260</u>	14 Nearest source of possible contamination: ft. Direction Type Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
			<u>10' fine sand - strips of sandy clay</u>	<u>260</u>	<u>270</u>	15 Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Goulds</u> Model number <u>120MC</u> HP volts Length of drop pipe <u>290</u> ft. capacity <u>420</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
			<u>7' fine sand 3' sandy clay</u>	<u>270</u>	<u>280</u>	17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Jack Bone Drilling Inc</u> 197 Business name License No. Address <u>McDonald Ks</u> Signed <u>Jack Bone</u> Date <u>7-15-75</u> Authorized representative
			<u>10' fine to med sand little sandy clay</u>	<u>280</u>	<u>290</u>	
			<u>4' fine sand & sandy clay 6' gravel</u>	<u>290</u>	<u>300</u>	
			<u>3' gravel 3' shale</u>	<u>300</u>	<u>306</u>	
16 Remarks: elevation Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley			(use a second sheet if needed)			