

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Cloud	NW ¼ NW ¼ NW ¼	24	T 6 S	R 3 NW

Distance and direction from nearest town or city street address of well if located within city?

3 miles South & 1 mile East of Concordia, Ks.

2 WATER WELL OWNER: **Joe Reedy**
 RR#, St. Address, Box # : **1926 Teal Rd.** Board of Agriculture, Division of Water Resources
 City, State, ZIP Code : **Concordia, Ks. 66901** Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

	4 DEPTH OF COMPLETED WELL 130 ft. ELEVATION: Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 35 ft. below land surface measured on mo/day/yr 4/18/05 Pump test data: Well water was ft. after hours pumping gpm Est. Yield 35-40 gpm: Well water was ft. after hours pumping gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well X Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes X No
--	---

5 TYPE OF BLANK CASING USED:

1 Steel	3 RMP (SR)	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
X PVC	4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded
		7 Fiberglass		Threaded

Blank casing diameter **5** in. to **1.10** ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface **12** in., weight **2.37** lbs./ft. Wall thickness or gauge No. **.214**

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel	3 Stainless Steel	5 Fiberglass	X PVC	10 Asbestos-Cement
2 Brass	4 Galvanized Steel	6 Concrete tile	8 RMP (SR)	11 Other (Specify)
			9 ABS	12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot	X Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes	
		7 Torch cut	10 Other (specify) ft.

SCREEN-PERFORATED INTERVALS: From **1.10** ft. to **130** ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From **20** ft. to **130** ft., From ft. to ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout **X** Bentonite 4 Other

Grout Intervals: From **0** ft. to **20** ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination: **None within 1/4 mile**

1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	

Direction from well? How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Topsoil			
2	15	Sand, rock & shale layers			
15	23	Shale w/ sandstone layers			
23	50	Red, white, blue shale			
50	85	Shale, gray w/sandstone layers			
85	103	Sandstone, tan/soft			
103	107	Sandstone, red/soft			
107	125	Sandstone, tan/soft			
125	130	Shale, gray			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was **X** constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **4/18/05** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No **138** This Water Well Record was completed on (mo/day/yr) **4/28/05** under the business name of **Peterson Irrigation, Inc.** by (signature) *Mike Peterson*