

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

Job #282-77-C-13-7-31

BDC

1. Location of well:		County Sheridan	Fraction SW 1/4 SE 1/4 NW 1/4	Section number 11	Township number T 7 S R 30	Range number 30
2. Distance and direction from nearest town or city: Rexford; 5 1/4 E; 1/2 S to well			3. Owner of well: Evelyn Seifert			
Street address of well location if in city:			R.R. or street:			
			City, state, zip code: Ravenna, NE 68869			
4. Locate with "X" in section below:			Sketch map:			6. Bore hole dia. 30 in. Completion date 3-28-78
						Well depth 225 ft.
						7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input checked="" type="checkbox"/> Reverse rotary
						<input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored
						8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
						9. Casing: Material Steel Height: Above or below xxx
						Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in.
						RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 188 lbs./ft.
						Dia. 16 in. to 155 ft. depth Wall Thickness: inches or
						Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. #7
5. Type and color of material			From	To	10. Screen: Manufacturer's name Brown	
Coarse Sand, Clay			0	100	Type Bridge Dia. 16"	
Fine Sand, Sandy Clay w/limestone Streaks			100	120	Slot/gauze 10% Length 60'	
Coarse Sand, Clay Streaks			120	140	Set between 155 ft. and 215 ft.	
Fine to Coarse Sand, Clay			140	160	10' Cook ft. and 225 ft.	
Clay, Limestone with Fine Sand			160	186	Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/2 x 5/8	
Coarse Sand, Med. Gravel with Clay Streaks			186	209	11. Static water level: 107 ft. below land surface Date 3-30-78	
Clay			209	213	12. Pumping level below land surfaces:	
Coarse Sand, Med. Gravel, Clay Streaks			213	223	142 ft. after 1 hrs. pumping 798 g.p.m.	
Ochre, Shale			223	225	220 ft. after 1 hrs. pumping 1280 g.p.m.	
					Estimated maximum yield 1280 g.p.m.	
					13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date	
					14. Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade	
					15. Well grouted? <input checked="" type="checkbox"/> X	
					With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete	
					Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: 3/4M Direction E Type Farmstead	
					Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
					17. Pump: <input type="checkbox"/> Not installed	
					Manufacturer's name Floway	
					Model number 10 DOH HP 80 Volts	
					Length of drop pipe 210 ft. capacity <input type="checkbox"/> g.p.m.	
					Type: 10 Stage 10 DOH	
					<input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine	
					<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating	
					<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
18. Elevation:			19. Remarks:			20. Water well contractor's certification:
Topography:						This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
<input type="checkbox"/> Hill						Western Well & Pump 245
<input type="checkbox"/> Slope						Business name Western Well & Pump License No. 245
<input checked="" type="checkbox"/> Upland						Address Box 852 Colby, KS 67701
<input type="checkbox"/> Valley						Signed Ann Houston Date 4/24/78
						Authorized representative

BROCK 223'

7
30
11
SW SE NW
1/4
1/4
1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5