


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

AAB

1 Location of well:	County <i>Sheridan</i>	Township name <i>Bloomfield</i>	Section number <i>NE 1/4</i>	Town number <i>7</i>	Range number <i>30</i>
Distance and direction from nearest town or city: <i>3 EAST, 2 South</i>			3 Owner of well: <i>Luman Bogg</i>		
Street address of well location if in city: <i>2 East of Ruffalo Co.</i>			Address: <i>Selden, Kansas 67757</i>		
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:		
2 Type and color of material			From	To	4 Well depth: <i>278</i> ft. Date of completion <i>5-75</i> Well diameter <i>28</i> in.
<i>Top Soil</i>			<i>0</i>	<i>155</i>	5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
<i>Fine sand, med gravel, sandy clay sandstone</i>			<i>155</i>	<i>175</i>	6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>
<i>Fine sand, med gravel, sandy clay sandstone</i>			<i>175</i>	<i>195</i>	7 Casing: Material <i>Steel</i> Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <i>12</i> in. Diam. <i>33</i> lbs./ft. L <i>0</i> in. to <i>278</i> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No ___ in. to ___ ft. depth
<i>" " Med gravel (loose colored)</i>			<i>195</i>	<i>209</i>	8 Screen: Manufacturer <i>W.A.B. Brown</i> Type <i>Lower</i> Dia. <i>16</i> Slot/gauge <i>2-18</i> Length <i>60</i> Set between <i>218</i> ft. and ___ ft. <i>278</i> Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <i>1/4 x 5/8</i>
<i>" " " " " "</i>			<i>209</i>	<i>215</i>	9 Static water level: <i>155</i> ft. below land surface Date <i>4-9-75</i>
<i>" " " " " "</i>			<i>215</i>	<i>226</i>	10 Pumping level below land surfaces: <i>274</i> ft. after <i>5</i> hrs. pumping <i>1250</i> g.p.m. ___ ft. after ___ hrs. pumping ___ g.p.m. Estimated maximum yield <i>1250</i> g.p.m.
<i>Fine sand med gravel, sandy clay (loose colored)</i>			<i>226</i>	<i>235</i>	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ___
<i>" " " " " "</i>			<i>235</i>	<i>245</i>	12 Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> <i>12</i> inches above grade
<i>" " " " " "</i>			<i>245</i>	<i>253</i>	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From <i>0</i> ft. to <i>10</i> ft.
<i>Fine sand Sandy clay</i>			<i>253</i>	<i>255</i>	14 Nearest source of possible contamination: ft. ___ Direction ___ Type <i>None</i> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
<i>Fine sand, med gravel (loose colored)</i>			<i>255</i>	<i>266</i>	15 Pump: <input type="checkbox"/> Not installed Manufacturer's name <i>Goetts</i> Model number <i>8X162</i> HP <i>100</i> Volts ___ Length of drop pipe <i>270</i> ft. capacity ___ g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
<i>" " " " " "</i>			<i>266</i>	<i>268</i>	
<i>Fine sand med gravel (loose colored)</i>			<i>268</i>	<i>275</i>	
<i>" " " " " "</i>			<i>275</i>	<i>278</i>	
<i>Ocher - Shale</i>			<i>278</i>	<i>295</i>	
(use a second sheet if needed)					
16 Remarks: elevation <i>BROCK 278</i>			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>Blue Jay Drilling Inc 214</i> Business name License No. ___ Address <i>3rd 503 Colby Kans.</i> Signed <i>Marshall Ralbe</i> Date <i>6-2-75</i> Authorized representative		

7 30W 27 N 29E