

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

CDD

| | | | | | | |
|---|--------------|---------------------------|--|--|--------------------------------------|---------------------------|
| 1. Location of well: | | County Sheridan | Fraction SE 1/4 SE 1/4 SW 1/4 | Section number 36 | Township number T 7 S R 30 | Range number 30 |
| 2. Distance and direction from nearest town or city: From Hoxie, KS; 2 1/2 North; 9 1/2 West <small>Street address of well location if in city:</small> | | | 3. Owner of well: Earl Moss R.R. or street: City, state, zip code: Menlo, Kansas | | | |
| 4. Locate with "X" in section below: | | Sketch map: | | 6. Bore hole dia. 30 in. Completion date 9-14-76 Well depth 261 ft. | | |
| | | | | 7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary | | |
| | | | | 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other | | |
| 5. Type and color of material | | From | To | 9. Casing: Material Steel Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 188 lbs./ft. Dia. 16 in. to 17 1/4 in. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. #7 | | |
| Soil & Clay | | 0 | 80 | 10. Screen: Manufacturer's name Brown Type Regular Dia. 16" Slot/gauze 10% Length 80' Set between 17 1/4 ft. and 251 ft. 10" Cook 251 ft. and 261 ft. | | |
| Gravel | | 80 | 110 | Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/2 x 5/8 | | |
| Sandy Clay | | 110 | 140 | 11. Static water level: 147 ft. below land surface Date 9-18-76 mo./day/yr. | | |
| Med. Sand, Clay Streaks | | 140 | 160 | 12. Pumping level below land surfaces: 256 ft. after 2 hrs. pumping 1697 g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield 1697 g.p.m. | | |
| Gravel | | 160 | 169 | 13. Water sample submitted: mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date | | |
| Sandy Clay, Sand Stone | | 169 | 220 | 14. Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade | | |
| Gravel | | 220 | 246 | 15. Well grouted? <input checked="" type="checkbox"/> Clay With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft. | | |
| Rock | | 246 | 247 | 16. Nearest source of possible contamination: ft. 1300 Direction SE Type Farm Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | |
| Gravel | | 247 | 255 | 17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Floway Model number 056182 HP 100 Volts 480 Length of drop pipe 2 ft. capacity ____ g.p.m. Type: 5 stage <input checked="" type="checkbox"/> 12" DOH <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | | |
| Yellow Clay, Shale | | 255 | 261 | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Western Well & Pump 245 Business name License No. Address Box 857, Colby, KS Signed Sally Berry Date 10-29-76 Authorized representative | | |
| (Use a second sheet if needed) | | | | | | |
| 18. Elevation: | 19. Remarks: | | 20. Water well contractor's certification: | | | |
| Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley | | | | | | |

1-7
 300
 36
 Sec
 1/4
 1/4
 1/4