


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

| | | | | | |
|--|-------------------------|--------------------------------|---|-------------------------|---|
| 1 Location of well: | County Thomas | Township name Rovohl | Section number 9 | Town number 7 | Range number 34W |
| Distance and direction from nearest town or city: 3 1/2 miles West; 4 1/2 miles North Street address of well location if in city: | | | 3 Owner of well: Vincent Glad Address: Colby, Kansas | | |
| Locate with "X" in section below:  | | | Sketch map: | | |
| 2 Type and color of material | | | From | To | 4 Well depth: 171 ft. Date of completion: 1/14/76 Well diameter 30 in. |
| Clay | | | 0 | 59 | 5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary |
| Medium to coarse sand & gravel | | | 59 | 72 | 6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well |
| Clay | | | 72 | 74 | 7 Casing: Material Steel Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. Diam. 16 in. to 81 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No _____ in. to _____ ft. depth |
| Medium to coarse sand & gravel | | | 74 | 83 | 8 Screen: Manufacturer Brown 10' Cook Type Regular Dia. 16" Slot/gauze 10% Length 161' 80 <input checked="" type="checkbox"/> Set between 81 ft. and 161' 171 Cook Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 1/2 X 5/8 50% #1 |
| Clay | | | 83 | 89 | 9 Static water level: 64 ft. below land surface Date 1/14/76 |
| Medium to coarse sand & gravel | | | 89 | 113 | 10 Pumping level below land surfaces: 160 ft. after 2 hrs. pumping 599 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m. |
| Clay & medium to coarse sand streaks | | | 113 | 121 | 11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____ |
| Coarse sand and gravel | | | 121 | 132 | 12 Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade 12 |
| Sand stone | | | 132 | 134 | 13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Clay Depth: From _____ ft. to 10 ft. |
| Coarse sand & gravel | | | 134 | 138 | 14 Nearest source of possible contamination: ft. 2600 Direction South Type Farm Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |
| Sand stone | | | 138 | 141 | 15 Pump: <input type="checkbox"/> Not installed Manufacturer's name Floway 2-13-76 Model number 7620 HP 100 Volts _____ Length of drop pipe 160 ft. capacity 550 g.m.p. Type: 12 stage 10" DOH bowl <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other |
| Coarse sand & gravel | | | 141 | 147 | 17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. |
| Medium sand & sand stone & clay | | | 147 | 157 | Western Well and Pump 245 Business name _____ License No. _____ Address P.O. Box 852 Colby, Ks. Signed Billy Berry Date 3-22-76 Authorized representative |
| Medium to coarse sand- white | | | 157 | 169 | |
| Ochre & Shale | | | 169 | 180 | |
| 16 Remarks: elevation BROCK 169' Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley | | | | | |

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5