


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Thomas	Fraction SE 1/4 SE 1/4 SE 1/4	Section number 18	Township number T 7 S	Range number R 34 E/W
2. Distance and direction from nearest town or city: From Hwy 24-25 in Colby; 4 West; 3 North; 1 West Street address of well location if in city:			3. Owner of well: Ferguson Trust R.R. or street: City, state, zip code: Colby, Kansas		
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W E S 1 Mile</div> 			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. 30 in. Completion date 10-5-76 Well depth 178 ft.
Clay, Coarse Sand, Gravel			0	60	7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Coarse Sand, Gravel			60	72	8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other <input type="checkbox"/>
Clay			72	75	9. Casing: Material Steel Height: Above XXXX Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 188 lbs./ft. Dia. 16 in. to 88 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. #7
Sand Stone			75	77	10. Screen: Manufacturer's name Brown Type Regular Dia. 16" Slot/gauze 10% Length 80' Set between 88 ft. and 168 ft. 10' Cook 168 ft. and 178 ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/2 5/8 #30 #1
Coarse Sand, Gravel			77	86	11. Static water level: <input type="checkbox"/> mo./day/yr. 64 ft. below land surface Date 10-6-76
Sandy Clay			86	93	12. Pumping level below land surfaces: 175 ft. after 2 hrs. pumping 1280 g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1280 g.p.m.
Coarse Sand, Gravel			93	100	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
Coarse Sand, Gravel, Clay			100	120	14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade
Coarse Sand, Gravel, Clay, Sandstone			120	140	15. Well grouted? <input checked="" type="checkbox"/> With: Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Clay <input checked="" type="checkbox"/> Depth: From 0 ft. to 10 ft.
Clay			145	150	16. Nearest source of possible contamination: ft. 6000 Direction E-NE Type Farm Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Coarse Sand, Gravel			150	178	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Floway Model number 056219 HP 125 Volts 480 Length of drop pipe 160 ft. capacity <input type="checkbox"/> g.p.m. Type: 8 Stage 12" DOL <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Western Well & Pump 245 Business name License No. Address Box 852, Colby, KS Signed Dolly Berry Date 11/12/76 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5