

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

LEVANT

WATER WELL RECORD  
KSA 82a-1201-1215

BAC

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well:	County <b>Thomas</b>	Township name <b>Barrett</b>	Fraction <b>NE 1/4 of NW 1/4</b>	Section number <b>3</b>	Town number <b>T-7-S-R-</b>	Range number <b>35-W</b>
Distance and direction from nearest town or city: Street address of well location if in city:			3 Owner of well: <b>Roland Rush</b> <b>Levant, KS.</b>			
Locate with "X" in section below: N W E S 1 Mile			4 Well depth: <b>258</b> ft. Date of completion <b>4-1-75</b> Well diameter <b>28</b> in. 5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary 6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well 7 Casing: Material <b>Steel</b> Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. Diam. <b>7</b> gauge/ft. <b>0</b> in. to <b>170</b> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No in. to in. ft. depth			
2 Type and color of material			From	To	8 Screen: Manufacturer <b>W.A. Brown</b> Type <b>Bridge</b> Dia. <b>16"</b> Slot/gauze <b>178</b> Length <b>2"</b> Set between <b>170</b> ft. and <b>248</b> ft. Fittings: <b>10' Cook - 248-258</b> Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <b>1/4 x 5/8</b>	
Clay and sand streaks			0	115	9 Static water level: <b>129</b> ft. below land surface Date <b>1-17-75</b>	
Fine to coarse sand and gravel			115	120	10 Pumping level below land surfaces: <b>248</b> ft. after <b>2</b> hrs. pumping <b>725</b> g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield <b>725</b> g.p.m.	
Sandy clay			120	140	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date	
Cemented sand			140	143	12 Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> inches above grade	
Clay and cemented sand streaks			143	160	13 Well grouted? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> & clay Depth: From <b>0</b> ft. to <b>10</b> ft.	
Fine to coarse sand and gravel			160	165	14 Nearest source of possible contamination: ft. <b>2500</b> Direction <b>Northwest</b> Type <b>Home</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Clay			165	170	15 Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Byron Jackson</b> Model number <b>8"</b> HP <b>100</b> Volts Length of drop pipe <b>250</b> ft. capacity g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Fine to coarse sand and gravel			170	176	17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Western Well &amp; Pump, Inc. 245</b> Business name <b>Box 852 Colby, KS.</b> License No. Address Signed <b>Roy E. Jensen</b> Date <b>6-14-75</b> Authorized representative	
Clay			176	187		
Fine to coarse sand and gravel			187	190		
Clay			190	195		
Clay and cemented sand streaks			195	199		
Fine to coarse sand and gravel			199	205		
Clay and cemented streaks			205	210		
Sandy clay			210	215		
Fine to coarse sand (and gravel if needed)			215	258		
16 Remarks: elevation <b>3307 (topo)</b> <b>BROOK ?</b> Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5