

1 LOCATION OF WATER WELL		Fraction SE ¼ NE ¼ SE ¼		Section Number 10		Township Number T 7 S		Range Number R 35 E/W																																																																									
County: Thomas				Distance and direction from nearest town or city? Levant 5¼ North; ½ West				Street address of well if located within city? N/A																																																																									
2 WATER WELL OWNER:		Kenneth Crampton																																																																															
RR#, St. Address, Box # :		Board of Agriculture, Division of Water Resources																																																																															
City, State, ZIP Code :		Levant, KS 67743																																																																															
		Application Number: 32,020																																																																															
3 DEPTH OF COMPLETED WELL:		250 ft. Bore Hole Diameter: 30 in. to 250 ft. and in. to ft.																																																																															
Well Water to be used as:		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well																																																																															
Well's static water level		-18 ft. below land surface measured on 12 month 18 day 79 year																																																																															
Pump Test Data		Well water was ft. after 2½ hours pumping 972 gpm																																																																															
Est. Yield 970 gpm		Well water was 157 ft. after 3 ½ hours pumping 636 gpm																																																																															
4 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile Casing Joints: Glued Clamped 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded 2 PVC 4 ABS 7 Fiberglass Threaded																																																																															
Blank casing dia		16 in. to 160 ft. Dia in. to ft. Dia in. to ft.																																																																															
Casing height above land surface		12 in., weight 32 lbs./ft. Wall thickness or gauge No. 188																																																																															
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)																																																																															
Screen or Perforation Openings Are:		5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)																																																																															
Screen-Perforation Dia		16 in. to ft. Dia in. to ft. Dia in. to ft.																																																																															
Screen-Perforated Intervals:		4 From 150 ft. to 240 ft. From ft. to ft. 6 From 240 ft. to 250 ft. From ft. to ft.																																																																															
Gravel Pack Intervals:		From ft. to ft. From ft. to ft. From 10 ft. to 250 ft. From ft. to ft.																																																																															
5 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other Concrete																																																																															
Grouted Intervals: From		0 ft. to 10 ft. From ft. to ft. From ft. to ft.																																																																															
What is the nearest source of possible contamination:		10 Fuel storage 14 Abandoned water well 11 Fertilizer storage 15 Oil well/Gas well 12 Insecticide storage 16 Other (specify below) 13 Watertight sewer lines Farmstead																																																																															
Direction from well		S How many feet 1200 ? Water Well Disinfected? Yes No X																																																																															
Was a chemical/bacteriological sample submitted to Department?		Yes No X If yes, date sample was submitted month day year Pump Installed? Yes X No																																																																															
If Yes: Pump Manufacturer's name		A & C Tait Model No. S-12HCC HP Volts																																																																															
Depth of Pump Intake		242 ft. Pumps Capacity rated at 800 gal./min.																																																																															
Type of pump:		1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other																																																																															
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:		This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 12 month 16 day 79 year																																																																															
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No.		245																																																																															
This Water Well Record was completed on		1 month 25 day 80 year under the business name of Western Well & Pump, Inc. by (signature) Roy F. Senior																																																																															
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>65</td> <td>Clay</td> <td>244</td> <td>255</td> <td>Shale</td> </tr> <tr> <td>65</td> <td>96</td> <td>Sand, Gravel, Clay, Cement</td> <td></td> <td></td> <td></td> </tr> <tr> <td>96</td> <td>122</td> <td>Clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>122</td> <td>130</td> <td>Coarse Sand & Gravel</td> <td></td> <td></td> <td></td> </tr> <tr> <td>130</td> <td>149</td> <td>Clay, Sand & Cement</td> <td></td> <td></td> <td></td> </tr> <tr> <td>149</td> <td>163</td> <td>Md. Sand & Sandstone ST.</td> <td></td> <td></td> <td></td> </tr> <tr> <td>163</td> <td>171</td> <td>Coarse Sand & Gravel</td> <td></td> <td></td> <td></td> </tr> <tr> <td>171</td> <td>203</td> <td>White Clay, Sand, Sandstone St.</td> <td></td> <td></td> <td></td> </tr> <tr> <td>203</td> <td>219</td> <td>Coarse Sand & Gravel</td> <td></td> <td></td> <td></td> </tr> <tr> <td>219</td> <td>229</td> <td>Clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>229</td> <td>244</td> <td>Coarse Sand & Gravel</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>								FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	0	65	Clay	244	255	Shale	65	96	Sand, Gravel, Clay, Cement				96	122	Clay				122	130	Coarse Sand & Gravel				130	149	Clay, Sand & Cement				149	163	Md. Sand & Sandstone ST.				163	171	Coarse Sand & Gravel				171	203	White Clay, Sand, Sandstone St.				203	219	Coarse Sand & Gravel				219	229	Clay				229	244	Coarse Sand & Gravel			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG																																																																												
0	65	Clay	244	255	Shale																																																																												
65	96	Sand, Gravel, Clay, Cement																																																																															
96	122	Clay																																																																															
122	130	Coarse Sand & Gravel																																																																															
130	149	Clay, Sand & Cement																																																																															
149	163	Md. Sand & Sandstone ST.																																																																															
163	171	Coarse Sand & Gravel																																																																															
171	203	White Clay, Sand, Sandstone St.																																																																															
203	219	Coarse Sand & Gravel																																																																															
219	229	Clay																																																																															
229	244	Coarse Sand & Gravel																																																																															
ELEVATION:																																																																																	
Depth(s) Groundwater Encountered		1. ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)																																																																															

INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.