


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

BAD

1 Location of well:	County <u>SHERMAN</u>	Township name <u>LOGAN SE NE 1/4 NW 1/4</u>	Fraction <u>3/4</u>	Section number <u>37</u>	Town number <u>T 75</u>	Range number <u>40</u>
Distance and direction from nearest town or city: <u>Goodland</u> Street address of well location if in city: <u>3rd St NW 1/4</u> <u>4th and 2 1/2 W</u>			3 Owner of well: <u>Chuck Thrig</u> Address: <u>Goodland Kansas</u>			
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:			4 Well depth: <u>291</u> ft. Date of completion <u>1-28-75</u> Well diameter <u>26</u> in.
2 Type and color of material			From	To	5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
<u>Fine Sand, Gravel, Sandy Clay</u>			<u>89</u>	<u>98</u>	6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well	
<u>Fine Sand, M Gravel, Sandy Clay</u>			<u>98</u>	<u>126</u>	7 Casing: Material <u>Steel</u> Height: <u>above</u> below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. Diam. <u>16</u> in. to <u>291</u> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Weight <u>33</u> lbs./ft. L	
<u>Fine Sand, Gravel, Sandy Clay</u>			<u>126</u>	<u>136</u>	8 Screen: Manufacturer <u>W. A. Brown</u> Type <u>Luxor</u> Dia. <u>16</u> Slot/gauze <u>1/8 - 7</u> Length <u>110</u> Set between <u>177</u> ft. and <u>287</u> ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <u>1/4 - 5/8</u>	
<u>Fine Sand, Sandy Clay, Sandstone</u>			<u>136</u>	<u>165</u>	9 Static water level: <u>129</u> ft. below land surface Date <u>1-29-75</u>	
<u>M Gravel, Sandy Clay, H Sandstone</u>			<u>165</u>	<u>184</u>	10 Pumping level below land surfaces: <u>250</u> ft. after <u>4</u> hrs. pumping <u>1400</u> g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield <u>1700</u> g.p.m.	
<u>Fine Sand, M Gravel</u>			<u>184</u>	<u>194</u>	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ____	
<u>Fine Sand, M Gravel, Sandstone</u>			<u>194</u>	<u>204</u>	12 Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade	
<u>Fine Sand, Gravel, Sandy Clay</u>			<u>204</u>	<u>243</u>	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> ____ Depth: From <u>0</u> ft. to <u>10</u> ft.	
<u>Fine Sand, M Gravel, Sandstone</u>			<u>243</u>	<u>252</u>	14 Nearest source of possible contamination: ft. ____ Direction ____ Type <u>None</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
<u>Fine Sand, Sandstone</u>			<u>252</u>	<u>281</u>	15 Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Western Land Reclamation</u> Model number <u>6M</u> HP <u>90</u> Volts ____ Length of drop pipe <u>270</u> ft. capacity <u>700</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
<u>Fine Sand, M Gravel, Sandstone</u>			<u>281</u>	<u>287</u>	17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>St H Dilling Co Inc</u> <u>116</u> Business name License No. Address <u>Goodland Kan.</u> Signed <u>Rick Dilling</u> Date <u>2-4-75</u> Authorized representative	
<u>Ochre</u>			<u>287</u>	<u>291</u>		
16 Remarks: elevation <u>3674 (TOTO)</u> Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						