

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

ACC

1. Location of well: <i>House</i>	County <i>Shawnee</i>	Fraction <i>SW 1/4 SW 1/4 NE 1/4</i>	Section number <i>11</i>	Township number <i>T 8 S R 30 E</i>	Range number <i>30 E</i>
2. Distance and direction from nearest town or city: <i>19 N 1/2 W</i>		3. Owner of well: <i>Francis Beckman</i>			
Street address of well location if in city: <i>Brimmell</i>		R.R. or street: <i>R. Menlo. Ks.</i>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <i>9</i> in. Completion date <i>8-20-95</i> Well depth <i>282</i> ft.	
				7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
5. Type and color of material		From	To	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
<i>Top soil</i>		<i>0</i>	<i>37</i>	9. Casing: Material _____ Height: Above or below Threaded <input type="checkbox"/> Welded _____ Surface <i>4</i> in. RMP _____ PVC <input checked="" type="checkbox"/> Weight _____ lbs./ft. Dia. _____ in. to _____ ft. depth Wall Thickness: inches or Dia. <i>5</i> in. to <i>282</i> ft. depth gage No. <i>200</i>	
<i>sandy clay</i>		<i>37</i>	<i>50</i>	10. Screen: Manufacturer's name <i>Gess Jewell</i> Type <i>PVC</i> Dia. <i>5</i> Slot/gauze <i>1/32</i> Length <i>8'</i> Set between <i>272</i> ft. and <i>280</i> ft. _____ ft. and _____ ft.	
<i>gravel</i>		<i>50</i>	<i>74</i>	Gravel pack? <input checked="" type="checkbox"/> Size range of material <i>1/8-1/4</i>	
<i>sandy clay</i>		<i>74</i>	<i>89</i>	11. Static water level: _____ mo./day/yr. <i>160</i> ft. below land surface Date _____	
<i>gravel</i>		<i>89</i>	<i>94</i>	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <i>30 +</i> g.p.m.	
<i>sandy clay</i>		<i>94</i>	<i>109</i>	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
<i>gravel</i>		<i>109</i>	<i>112</i>	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <i>12</i> Inches above grade	
<i>sandy clay</i>		<i>112</i>	<i>144</i>	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <i>0</i> ft. to <i>10</i> ft.	
<i>fine sand & sandy clay</i>		<i>144</i>	<i>165</i>	16. Nearest source of possible contamination: <i>none</i> ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
<i>m. gravel</i>		<i>165</i>	<i>176</i>	17. Pump: _____ Not installed Manufacturer's name <i>Goulds</i> Model number <i>108J</i> HP <i>1</i> Volt <i>220</i> Length of drop pipe <i>222</i> ft. capacity <i>15</i> g.p.m. Type: <input checked="" type="checkbox"/> Submersible _____ Turbine <input type="checkbox"/> Jet _____ Reciprocating <input type="checkbox"/> Centrifugal _____ Other	
<i>fine sand & m gravel</i>		<i>176</i>	<i>185</i>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>Stankhoff Lewis</i> <i>298</i> Business name _____ License No. _____ Address <i>Brimmell</i> Signed <i>Stankhoff</i> Date <i>7-28</i> Authorized representative	
<i>sandy clay & S.S.</i>		<i>185</i>	<i>194</i>		
<i>gravel</i>		<i>194</i>	<i>204</i>		
<i>sandy clay</i>		<i>204</i>	<i>209</i>		
<i>S.S.</i>		<i>209</i>	<i>218</i>		
<i>sandy clay & S.S. (Use a second sheet if needed)</i>		<i>218</i>	<i>255</i>		
18. Elevation:	19. Remarks: <i>gravel, Office.</i>		<i>255-280</i> <i>280-282</i>		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	<i>BROCK 280</i>				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

2
300
11
SW 1/4 NE
1/4
1/4
26