


1 LOCATION OF WATER WELL		Fraction	Section Number		Township Number		Range Number						
County: Thomas		NE 1/4 NE 1/4 SE 1/4	15		T 8 S		R 31 E/W						
Distance and direction from nearest town or city? Menlo 2 West			Street address of well if located within city? N/A										
2 WATER WELL OWNER: Al Meier													
RR#, St. Address, Box # :			Board of Agriculture, Division of Water Resources										
City, State, ZIP Code : Menlo, KS 67746			Application Number: 30,900										
3 DEPTH OF COMPLETED WELL: 218 ft. Bore Hole Diameter: 28 in. to 218 ft. and in. to ft.													
Well Water to be used as:			5 Public water supply			8 Air conditioning							
1 Domestic 3 Feedlot			6 Oil field water supply			9 Dewatering							
2 Irrigation 4 Industrial			7 Lawn and garden only			10 Observation well							
Well's static water level: 124 ft. below land surface measured on 12 month 29 day 79 year			11 Injection well			12 Other (Specify below)							
Pump Test Data			Well water was: 200 ft. after 6 hours pumping 1000 gpm			Well water was: 200 ft. after 6 hours pumping 1000 gpm							
4 TYPE OF BLANK CASING USED:													
1 Steel			3 RMP (SR)			5 Wrought iron							
2 PVC			4 ABS			6 Asbestos-Cement							
						7 Fiberglass							
Blank casing dia: 16 in. to 138 ft. Dia						8 Concrete tile							
Casing height above land surface: 12 in., weight 32 lbs./ft. Wall thickness or gauge No. 188						9 Other (specify below)							
TYPE OF SCREEN OR PERFORATION MATERIAL:													
1 Steel			3 Stainless steel			5 Fiberglass							
2 Brass			4 Galvanized steel			6 Concrete tile							
						7 PVC							
						8 RMP (SR)							
						9 ABS							
						10 Asbestos-cement							
						11 Other (specify)							
						12 None used (open hole)							
Screen or Perforation Openings Are:													
1 Continuous slot			3 Mill slot			5 Gauzed wrapped							
2 Louvered shutter			4 Key punched			6 Wire wrapped							
						7 Torch cut							
						8 Saw cut							
						9 Drilled holes							
						10 Other (specify)							
						11 None (open hole)							
Screen-Perforation Dia: 16 in. to ft. Dia in. to ft. Dia in. to ft. Dia in. to ft.													
Screen-Perforated Intervals: 4 From 138 ft. to 208 ft. From ft. to ft. From ft. to ft. From ft. to ft.													
Gravel Pack Intervals: From 208 ft. to 218 ft. From ft. to ft. From ft. to ft. From ft. to ft.													
Gravel Pack Intervals: From 10 ft. to 218 ft. From ft. to ft. From ft. to ft. From ft. to ft.													
5 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Concrete													
Grouted Intervals: From 0 ft. to 10 ft. From ft. to ft. From ft. to ft. From ft. to ft.													
What is the nearest source of possible contamination:													
1 Septic tank			4 Cess pool			7 Sewage lagoon							
2 Sewer lines			5 Seepage pit			8 Feed yard							
3 Lateral lines			6 Pit privy			9 Livestock pens							
						10 Fuel storage							
						11 Fertilizer storage							
						12 Insecticide storage							
						13 Watertight sewer lines							
						14 Abandoned water well							
						15 Oil well/Gas well							
						16 Other (specify below)							
						Farmstead							
Direction from well SE How many feet 3000 ? Water Well Disinfected? Yes ☐ No ☒													
Was a chemical/bacteriological sample submitted to Department? Yes ☐ No ☒ If yes, date sample was submitted month day year: Pump Installed? Yes ☒ No ☐													
If Yes: Pump Manufacturer's name Floway Model No. 9-10DOH HP 70 Volts													
Depth of Pump Intake 200 ft. Pumps Capacity rated at 575 gal./min.													
Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other													
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 12 month 28 day 79 year													
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 245													
This Water Well Record was completed on 1 month 24 day 80 year under the business name of Western Well & Pump, Inc. by (signature) Roy F. Senior													
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM		TO		LITHOLOGIC LOG		FROM		TO		LITHOLOGIC LOG	
		0		48		Sand & Clay		205		215		Sand & Gravel	
		48		76		Sand & Gravel		205		230		Ochre & Shale	
		76		94		Clay & Sand Streaks							
		94		114		Sand & Gravel							
		114		134		Clay & Sand & Gravel							
		134		140		Clay							
		140		149		Sand & Gravel							
		149		151		Sandstone							
		151		169		Clay, Sand & Gravel Mix							
		169		190		Coarse Sand & Gravel Clay Streaks							
ELEVATION:		190		205		Sand, Gravel & Clay Mix, Sandstone Streaks							
Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)													
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.													